

**KING COUNTY HOUSING AUTHORITY
REQUEST FOR BID – BRITTANY PARK APARTMENTS M&E
WEATHERIZATION REPAIR PROJECTS**

ADDENDUM #2

Effective 06/24/2026. This Addendum #2 shall be considered part of the Request for Bid Documents for the Brittany Park Apartments Mechanical and Ventilation Request for Bids.

- Are the fire damper control wires connected to and monitored by the fire alarm system? – **yes** If so, are we responsible for providing and installing the wiring between the fire dampers and the fire alarm system?–**yes**
- Can you provide the required footage/lengths for:–***as far as measurements that should have been gathered at the bid walk. There is a scale on the plans and you can determine the measurements from those. I could schedule a walk if you would need to look at the areas in question again.***
 - Plug mold
 - Fire damper wiring
 - Ductwork
- Can we use 1/2" EMT instead of wire mold? –**yes**
- If conduit is acceptable, are there any specific requirements or restrictions regarding the installation method? –***if this question is for the in-unit Ephoca tower, tight to the ceiling and secure to the wall and ceiling.***
- We noted two disconnects located in the attic. Can you confirm if both disconnects are required as shown? –***yes-the plans show a disconnect for the supply and the exhaust in the attic.***
- Can the Titus grilles be substituted with Shoemaker grilles? We have worked with Shoemaker products on a previous project, and they are more readily available while offering comparable performance and appearance. – ***please follow the bid specifications***
- Are we supposed to frame around the unit or recess it into the wall? –***the Ephoca tower will be installed up against the wall, not recessed or framed. The custom cabinet from Thermaduct will be the finish and installed against the wall securely.***