

# Lead-Based Paint Inspection Report

Cedar Grove I  
816 Bingham Place  
Sedro-Woolley, Washington

Prepared for:  
Deborah McCaslin  
King County Housing  
700 Andover Park West, Suite C  
Seattle, Washington 98188

February 22, 2018  
PBS Project No. 40573.153



2517 EASTLAKE AVENUE EAST  
SUITE 100  
SEATTLE, WA 98102  
206.233.9639 MAIN  
866.727.0140 FAX  
PBSUSA.COM

LEAD-BASED PAINT INSPECTION REPORT

Cedar Grove I  
816 Bingham Place  
Sedro-Woolley, Washington

For

King County Housing Authority  
700 Andover Park West, Suite C  
Seattle, Washington 98188

This report is for the exclusive use of the client and is not to be photographed, photocopied, or similarly reproduced, in total or in part, without the express written consent of the client and/or PBS Engineering and Environmental Inc.

Prepared by:

PBS Engineering and Environmental Inc.  
2517 Eastlake Avenue East Suite 100  
Seattle, Washington 98102



**TABLE OF CONTENTS**

**1 IDENTIFYING INFORMATION.....1**

**2 LEAD-BASED PAINT INSPECTION.....2**

2.1 Site Information..... 2

2.2 Lead-Based Paint Inspection and Sampling ..... 2

    2.2.1 XRF Sampling..... 2

    2.2.2 Bulk Paint-Chip Sampling ..... 3

2.3 Components with Lead-Based Paint..... 3

2.4 Deteriorated Lead-Based Paint Surfaces..... 3

**SUPPORTING DATA**

**TAB 1: XRF Data Sheets**

**TAB 2: Certifications**

## 1 IDENTIFYING INFORMATION

### BUILDING DATA

Cedar Grove I  
816 Bingham Place  
Sedro-Woolley, Washington

### CLIENT DATA

King County Housing Authority  
700 Andover Park West, Suite C  
Seattle, WA 98188  
Attn: Ms. Deborah McCaslin

### SCOPE OF ASSESSMENT

PBS Engineering and Environmental, Inc. (PBS) conducted a lead-based paint inspection at Cedar Grove I on January 16, 2018, in accordance with the U.S. Department Housing and Urban Development (HUD), Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing.

### CERTIFICATIONS

#### Risk Assessor

Janet Murphy  
State of Washington  
Department of Community, Trade and Economic Development  
Risk Assessor Certification No: 0258, Expiration Date: 3/8/2019



Signature

February 22, 2018

Date

#### Firm

PBS Engineering and Environmental  
2517 Eastlake Avenue East  
Seattle, Washington 98102  
Telephone: 206.223.9639

Certification No: 129143  
Expiration Date: 7/31/2018

## 2 LEAD-BASED PAINT INSPECTION

### 2.1 Site Information

Cedar Grove I consists of three (3) buildings with a total of 10 units, a maintenance building with a community room. The buildings are of wood construction with gypsum interior walls and ceilings. The exterior is vinyl siding and vinyl trim. Apartment units are three and four bedrooms with a bathroom and a kitchen/dining room and living room area. The buildings are in good condition.

Architectural finishes are uniform throughout. The majority of the interior components are painted. Walls are painted gypsum wallboard. Doors are wood or metal. Door and window frames are painted medium density fiberboard (MDF) and metal. The exterior window frames are vinyl.

### 2.2 Lead-Based Paint Inspection and Sampling

Based on information provided by KCHA, Cedar Grove I was constructed in 1971. All buildings and units were found to have a similar construction and painting history. Based on Table 7.3 in Chapter 7 of the HUD Guidelines, 10 units at the site were included in PBS's inspection. Additionally, PBS inspected the building with the maintenance garage and community room and the playground.

#### 2.2.1 XRF Sampling

The presence of lead in paint was determined through x-ray fluorescence spectroscopy. A handheld Niton X-Ray Fluorescence Analyzer (XRF), Model XLP-300A Serial # 102877 operating in lead paint mode was used to perform a surface by surface lead paint inspection of each painted surface in the selected units and other building areas. Calibration was checked based on the requirements of the Performance Characteristic Sheet for the XRF Analyzer. All calibration readings were within the tolerance for this instrument.

HUD and the Environmental Protection Agency (EPA) have set 1.0 milligrams per square centimeter ( $\text{mg}/\text{cm}^2$ ) as the threshold limit for lead-based paint as determined through X-Ray Fluorescence (XRF) testing. HUD and EPA have set 5,000 parts per million (ppm) or 0.5 percent by atomic absorption spectroscopy (AAS) laboratory analysis as the threshold limit for lead-based paint. Paint that is known to contain lead levels less than those described above does not have to be evaluated, although all deteriorated paint (paint surfaces in poor condition) should be repaired because it may contain lower levels of lead that may contribute to lead dust or lead contaminated soil hazards.

The "Side" information presented on the XRF data sheets is in relation to the side of the rooms, or building exteriors where the unit address is located. The inspector/risk assessor used the address side of each residence as the basis to establish side "A". Sides B, C, and D follow in clockwise rotation.

Please refer to the XRF Sample Data Table located in Tab 1 for a complete list of XRF samples.

### **2.2.2 Bulk Paint-Chip Sampling**

Bulk paint chip verification samples were collected when there was an inconclusive result with the XRF. Inconclusive results were not recorded during the Cedar Grove I inspection.

### **2.3 Components with Lead-Based Paint**

None of the paint tested contained lead above the HUD level of 1.0 mg/cm<sup>2</sup> by XRF.

### **2.4 Deteriorated Lead-Based Paint Surfaces**

Lead-based paint was not identified at the subject property. Painted surfaces were evaluated to be in an intact condition.

**TAB 1**

---

**XRF Data Sheets**

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
1	Shutter Cal										6.21
2	nist standard	red paint								Positive	1
3	nist standard	red paint								Negative	0.9
4	nist standard	red paint								Positive	1
5	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	cedar grove unit 820	Negative	< LOD
6	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	cedar grove unit 820	Negative	< LOD
7	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	cedar grove unit 820	Negative	< LOD
8	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	cedar grove unit 820	Negative	< LOD
9	DOOR	METAL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	cedar grove unit 820	Negative	< LOD
10	DOOR FRAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	cedar grove unit 820	Negative	< LOD
11	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	cedar grove unit 820	Negative	< LOD
12	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	cedar grove unit 820	Negative	< LOD
13	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	cedar grove unit 820	Negative	< LOD
14	WINDOW	WOOD	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	cedar grove unit 820	Negative	< LOD
15	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	cedar grove unit 820	Negative	< LOD
16	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	cedar grove unit 820	Negative	< LOD
17	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	cedar grove unit 820	Negative	< LOD
18	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	cedar grove unit 820	Negative	< LOD
19	DOOR	WOOD	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	cedar grove unit 820	Negative	< LOD

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
20	DOOR FRAME	WOOD	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	cedar grove unit 820	Negative	< LOD
21	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 1	cedar grove unit 820	Negative	< LOD
22	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 1	cedar grove unit 820	Negative	< LOD
23	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 1	cedar grove unit 820	Negative	< LOD
24	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 1	cedar grove unit 820	Negative	< LOD
25	Window Sill	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 1	cedar grove unit 820	Negative	< LOD
26	DOOR	WOOD	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 1	cedar grove unit 820	Negative	< LOD
27	DOOR FRAME	WOOD	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 1	cedar grove unit 820	Negative	< LOD
28	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 2	cedar grove unit 820	Negative	< LOD
29	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 2	cedar grove unit 820	Negative	< LOD
30	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 2	cedar grove unit 820	Negative	< LOD
31	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 2	cedar grove unit 820	Negative	< LOD
32	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 2	cedar grove unit 820	Negative	< LOD
33	WINDOW SILL	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 2	cedar grove unit 820	Negative	< LOD
34	DOOR	WOOD	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 2	cedar grove unit 820	Negative	< LOD
35	DOOR FRAME	WOOD	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 2	cedar grove unit 820	Negative	< LOD
36	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	bathroom	cedar grove unit 820	Negative	< LOD
37	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	bathroom	cedar grove unit 820	Negative	< LOD
38	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	bathroom	cedar grove unit 820	Negative	< LOD

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
39	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	bathroom	cedar grove unit 820	Negative	< LOD
40	DOOR	WOOD	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	bathroom	cedar grove unit 820	Negative	< LOD
41	DOOR FRAME	WOOD	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	bathroom	cedar grove unit 820	Negative	< LOD
42	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	bathroom	cedar grove unit 820	Negative	< LOD
43	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 3	cedar grove unit 820	Negative	< LOD
44	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 3	cedar grove unit 820	Negative	0.7
45	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 3	cedar grove unit 820	Negative	< LOD
46	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 3	cedar grove unit 820	Negative	< LOD
47	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 3	cedar grove unit 820	Negative	< LOD
48	WINDOW SILL	WOOD	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 3	cedar grove unit 820	Negative	< LOD
49	CLOSET ROLL DOOR	WOOD	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 3	cedar grove unit 820	Negative	< LOD
50	DOOR	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 3	cedar grove unit 820	Negative	< LOD
51	DOOR FRAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 3	cedar grove unit 820	Negative	< LOD
52	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 4	cedar grove unit 820	Negative	< LOD
53	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 4	cedar grove unit 820	Negative	< LOD
54	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 4	cedar grove unit 820	Negative	< LOD
55	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 4	cedar grove unit 820	Negative	< LOD
56	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 4	cedar grove unit 820	Negative	< LOD
57	DOOR	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 4	cedar grove unit 820	Negative	< LOD

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
58	DOOR FRAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 4	cedar grove unit 820	Negative	< LOD
59	WINDOW SILL	WOOD	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 4	cedar grove unit 820	Negative	< LOD
60	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 1	cedar grove unit 820	Negative	< LOD
61	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 2	cedar grove unit 820	Negative	< LOD
62	RISER	WOOD	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 2	cedar grove unit 820	Negative	< LOD
63	BANISTER	WOOD	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	bedroom 2	cedar grove unit 820	Negative	< LOD
64	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	cedar grove unit 818	Negative	< LOD
65	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	cedar grove unit 818	Negative	< LOD
66	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	cedar grove unit 818	Negative	< LOD
67	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	cedar grove unit 818	Negative	< LOD
68	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	cedar grove unit 818	Negative	< LOD
69	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVINGROOM	cedar grove unit 818	Negative	< LOD
70	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVINGROOM	cedar grove unit 818	Negative	< LOD
71	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVINGROOM	cedar grove unit 818	Negative	< LOD
72	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVINGROOM	cedar grove unit 818	Negative	< LOD
73	WINDOW SILL	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVINGROOM	cedar grove unit 818	Negative	< LOD
74	DOOR	METAL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVINGROOM	cedar grove unit 818	Negative	< LOD
75	DOOR FRAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVINGROOM	cedar grove unit 818	Negative	< LOD
76	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	cedar grove unit 818	Negative	< LOD

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
77	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	cedar grove unit 818	Negative	< LOD
78	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	cedar grove unit 818	Negative	0.7
79	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	cedar grove unit 818	Negative	< LOD
80	DOOR	WOOD	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	cedar grove unit 818	Negative	< LOD
81	DOOR FRAME	WOOD	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	cedar grove unit 818	Negative	< LOD
82	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	cedar grove unit 818	Negative	< LOD
83	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	cedar grove unit 818	Negative	< LOD
84	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	cedar grove unit 818	Negative	< LOD
85	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	cedar grove unit 818	Negative	< LOD
86	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	cedar grove unit 818	Negative	< LOD
87	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	cedar grove unit 818	Negative	< LOD
88	DOOR	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	cedar grove unit 818	Negative	< LOD
89	DOOR FRAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	cedar grove unit 818	Negative	< LOD
90	WINDOW SILL	WOOD	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	cedar grove unit 818	Negative	< LOD
91	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	cedar grove unit 818	Negative	< LOD
92	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	cedar grove unit 818	Negative	< LOD
93	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	cedar grove unit 818	Negative	< LOD
94	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	cedar grove unit 818	Negative	< LOD
95	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	cedar grove unit 818	Negative	< LOD

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
96	DOOR	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	cedar grove unit 818	Negative	< LOD
97	DOOR FRAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	cedar grove unit 818	Negative	< LOD
98	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	cedar grove unit 818	Negative	< LOD
99	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	cedar grove unit 818	Negative	< LOD
100	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	cedar grove unit 818	Negative	< LOD
101	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	cedar grove unit 818	Negative	< LOD
102	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	cedar grove unit 818	Negative	< LOD
103	DOOR	WOOD	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	cedar grove unit 818	Negative	< LOD
104	DOOR FRAME	WOOD	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	cedar grove unit 818	Negative	< LOD
105	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	cedar grove unit 818	Negative	< LOD
106	NOT USED										
107	NOT USED										
108	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 818	Negative	0
109	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 818	Negative	0
110	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 818	Negative	0
111	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 818	Negative	0
112	WINDOW SILL	WOOD	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 818	Negative	0
113	DOOR	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 818	Negative	0
114	DOOR FRAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 818	Negative	0

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
115	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 818	Negative	0
116	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 818	Negative	0
117	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 818	Negative	0
118	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 818	Negative	0
119	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 818	Negative	0
120	DOOR	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 818	Negative	0
121	DOOR FRAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 818	Negative	0
122	WINDOW SILL	WOOD	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 818	Negative	0
123	RISER	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	STAIR	unit 818	Negative	0
124	HAND RAIL	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	STAIR	unit 818	Negative	0
125	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	FIRST	STAIR	unit 814	Negative	0
126	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	STAIR	unit 814	Negative	0.01
127	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	STAIR	unit 814	Negative	0
128	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	STAIR	unit 814	Negative	0
129	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	STAIR	unit 814	Negative	0
130	DOOR	METAL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVINGROOM	unit 814	Negative	0
131	DOOR FRAMR	METAL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVINGROOM	unit 814	Negative	0
132	WINDOW FRAME	METAL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVINGROOM	unit 814	Negative	0
133	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	unit 814	Negative	0.03

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
134	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	unit 814	Negative	0.08
135	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	unit 814	Negative	0.06
136	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	unit 814	Negative	0.03
137	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	unit 814	Negative	0
138	SLIDING DOOR FRAME	WOOD	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	unit 814	Negative	0
139	WINDOW SILL	WOOD	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	unit 814	Negative	0.05
140	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	unit 814	Negative	0
141	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	unit 814	Negative	0
142	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	unit 814	Negative	0.01
143	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	unit 814	Negative	0.01
144	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	unit 814	Negative	0
145	DOOR	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	SECOND	BATHROOM	unit 814	Negative	0
146	DOOR FRAME	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	SECOND	BATHROOM	unit 814	Negative	0
147	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	unit 814	Negative	0
148	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 814	Negative	0
149	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 814	Negative	0
150	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 814	Negative	0
151	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 814	Negative	0.7
152	WINDOW SILL	WOOD	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 814	Negative	0

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
153	DOOR	WOOD	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 814	Negative	0
154	DOOR FRAME	WOOD	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 814	Negative	0
155	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 814	Negative	0
156	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 814	Negative	0
157	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 814	Negative	0
158	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 814	Negative	0
159	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 814	Negative	0
160	WINDOW FRAME	WOOD	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 814	Negative	0
161	WINDOW FRAME	WOOD	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 814	Negative	0
162	DOOR	WOOD	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 814	Negative	0
163	DOOR FRAME	WOOD	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 814	Negative	0
164	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 814	Negative	0
165	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 814	Negative	0
166	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 814	Negative	0
167	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 814	Negative	0
168	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 814	Negative	0
169	WINDOW SILL	WOOD	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 814	Negative	0
170	DOOR	WOOD	B	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 814	Negative	0
171	DOOR FRAME	WOOD	B	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 814	Negative	0

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
172	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	HAL WALL	unit 814	Negative	0
173	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	HAL WALL	unit 814	Negative	0
174	CEILING	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	HAL WALL	unit 814	Negative	0
175	RISER	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	STAIR	unit 814	Negative	0
176	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	LIVING ROOM	unit 812	Negative	0
177	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	LIVING ROOM	unit 812	Negative	0
178	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	LIVING ROOM	unit 812	Negative	0.04
179	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	LIVING ROOM	unit 812	Negative	0
180	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	LIVING ROOM	unit 812	Negative	0.01
181	WINDOW SILL	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	LIVING ROOM	unit 812	Negative	0
182	DOOR	METAL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	LIVING ROOM	unit 812	Negative	0
183	DOOR FRAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	LIVING ROOM	unit 812	Negative	0
184	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	unit 812	Negative	0.01
185	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	unit 812	Negative	0.5
186	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	unit 812	Negative	0.02
187	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	unit 812	Negative	0.01
188	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	unit 812	Negative	0.3
189	CABINET	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	FIRST	KITCHEN	unit 812	Negative	0
190	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	unit 812	Negative	0.01

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
191	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	unit 812	Negative	0.05
192	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	unit 812	Negative	0.03
193	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	unit 812	Negative	0.03
194	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	unit 812	Negative	0.6
195	COLUMN	WOOD	B	INTACT	BROWN	CEDAR GROVE 1	FIRST	BATHROOM	unit 812	Negative	0
196	DOOR	WOOD	B	INTACT	BROWN	CEDAR GROVE 1	FIRST	BATHROOM	unit 812	Negative	0
197	DOOR FRAME	WOOD	B	INTACT	BROWN	CEDAR GROVE 1	FIRST	BATHROOM	unit 812	Negative	0
198	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 812	Negative	0
199	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 812	Negative	0.7
200	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 812	Negative	0.6
201	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 812	Negative	0
202	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 812	Negative	0
203	WINDOW SILL	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 812	Negative	0
204	DOOR	WOOD	C	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 812	Negative	0
205	DOOR FRAME	WOOD	C	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 812	Negative	0
206	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 812	Negative	0
207	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 812	Negative	0.7
208	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 812	Negative	0
209	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 812	Negative	0

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
210	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 812	Negative	0
211	WINDOW SIL	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 812	Negative	0
212	CLOSET ROLL DOOR	WOOD	C	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 812	Negative	0
213	DOOR	WOOD	D	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 812	Negative	0
214	DOOR FFAME	WOOD	D	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 812	Negative	0
215	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	unit 812	Negative	0.01
216	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	unit 812	Negative	0.6
217	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	unit 812	Negative	0.05
218	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	unit 812	Negative	0
219	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	unit 812	Negative	0.01
220	DOOR	WOOD	D	INTACT	BROWN	CEDAR GROVE 1	SECOND	BATHROOM	unit 812	Negative	0
221	DOOR FRAME	WOOD	D	INTACT	BROWN	CEDAR GROVE 1	SECOND	BATHROOM	unit 812	Negative	0
222	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 812	Negative	0
223	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 812	Negative	0
224	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 812	Negative	0
225	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 812	Negative	0
226	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 812	Negative	0
227	WINDOW SIL	WOOD	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 812	Negative	0
228	DOOR	WOOD	B	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 812	Negative	0

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
229	DOOR FRAME	WOOD	B	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 812	Negative	0
230	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 812	Negative	0
231	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 812	Negative	0
232	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 812	Negative	0
233	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 812	Negative	0.8
234	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 812	Negative	0
235	DOOR	WOOD	B	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 812	Negative	0
236	DOOR FRAME	WOOD	B	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 812	Negative	0
237	RISER	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	SECOND	STAIR	unit 812	Negative	0
238	HAND RAIL	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	SECOND	STAIR	unit 812	Negative	0
239	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	FIRST	STAIR	unit 810	Negative	0.6
240	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	unit 810	Negative	0.6
241	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	unit 810	Negative	0.6
242	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	unit 810	Negative	0
243	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	unit 810	Negative	0
244	DOOR	METAL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	unit 810	Negative	0
245	DOOR FAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	unit 810	Negative	0
246	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	unit 810	Negative	0.03
247	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	unit 810	Null	0.04

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
248	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	unit 810	Negative	0
249	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	unit 810	Negative	0
250	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	unit 810	Negative	0.04
251	CABINET	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	FIRST	KITCHEN	unit 810	Negative	0
252	WINDOW FLAME	WOOD	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	unit 810	Negative	0
253	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	unit 810	Negative	0.02
254	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	unit 810	Negative	0.08
255	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	unit 810	Negative	0.04
256	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	unit 810	Negative	0.12
257	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	unit 810	Negative	0.05
258	DOOR	WOOD	B	INTACT	BROWN	CEDAR GROVE 1	FIRST	BATHROOM	unit 810	Negative	0
259	DOOR FRAME	WOOD	B	INTACT	BROWN	CEDAR GROVE 1	FIRST	BATHROOM	unit 810	Negative	0.01
260	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 810	Negative	0
261	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 810	Negative	0
262	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 810	Negative	0
263	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 810	Negative	0
264	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 810	Negative	0
265	WINDOW SILL	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 810	Negative	0
266	DOOR	WOOD	C	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 810	Negative	0

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
267	DOOR FRAME	WOOD	C	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 810	Negative	0
268	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 810	Negative	0
269	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 810	Negative	0
270	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 810	Negative	0
271	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 810	Negative	0
272	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 810	Negative	0
273	WINDOW SILL	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 810	Negative	0.01
274	CLOSET ROLL DOOR	WOOD	C	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 810	Negative	0
275	COLUMN	WOOD	C	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 810	Negative	0
276	DOOR FRAME	WOOD	C	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 810	Negative	0
277	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	unit 810	Negative	0.02
278	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	unit 810	Negative	0.03
279	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	unit 810	Negative	0.01
280	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	unit 810	Negative	0.02
281	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	unit 810	Negative	0.03
282	DOOR	WOOD	D	INTACT	BROWN	CEDAR GROVE 1	SECOND	BATHROOM	unit 810	Negative	0
283	DOOR FRAME	WOOD	D	INTACT	BROWN	CEDAR GROVE 1	SECOND	BATHROOM	unit 810	Negative	0
284	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 810	Negative	0
285	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 810	Negative	0

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
286	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 810	Negative	0
287	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 810	Negative	0
288	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 810	Negative	0
289	WINDOW FRAME	WOOD	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 810	Negative	0
290	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 810	Negative	0
291	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 810	Negative	0
292	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 810	Negative	0
293	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 810	Negative	0
294	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 810	Negative	0
295	DOOR	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 810	Negative	0
296	DOOR FRAME	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 810	Negative	0
297	RISER	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	SECOND	STAIR	unit 810	Negative	0
298	HAND RAIL	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	SECOND	STAIR	unit 810	Negative	0
299	HAND RAIL	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	SECOND	STAIR	unit 810	Negative	0
300	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	unit 818	Negative	0.24
301	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	unit 818	Negative	0.02
302	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	unit 818	Negative	0.01
303	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	unit 818	Negative	0.05
304	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	unit 818	Negative	0.02

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
305	WINDOW SILL	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	unit 818	Negative	0
306	DOOR	METAL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	unit 818	Negative	0
307	DOOR FRAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	unit 818	Negative	0
308	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	unit 818	Negative	0
309	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	unit 818	Negative	0
310	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	unit 818	Negative	0.02
311	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	unit 818	Negative	0.03
312	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	unit 818	Negative	0.05
313	CABINET	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	FIRST	KITCHEN	unit 818	Negative	0
314	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	unit 818	Negative	0
315	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	unit 818	Negative	0
316	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	unit 818	Negative	0
317	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	unit 818	Negative	0
318	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM	unit 818	Negative	0.6
319	DOOR	WOOD	D	INTACT	BROWN	CEDAR GROVE 1	FIRST	BATHROOM	unit 818	Negative	0
320	DOOR FAME	WOOD	D	INTACT	BROWN	CEDAR GROVE 1	FIRST	BATHROOM	unit 818	Negative	0
321	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 818	Negative	0.02
322	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 818	Negative	0.03
323	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 818	Negative	0.04

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
324	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 818	Negative	0.1
325	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 818	Negative	0.01
326	WINDOW SILL	WOOD	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	unit 818	Negative	0.07
327	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 818	Negative	0.01
328	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 818	Negative	0.01
329	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 818	Negative	0.01
330	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 818	Negative	0.01
331	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 818	Negative	0.01
332	DOOR	WOOD	D	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 818	Negative	0.01
333	DOOR FRAME	WOOD	D	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 2	unit 818	Negative	0.05
334	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	unit 818	Negative	0
335	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	unit 818	Negative	0
336	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	unit 818	Negative	0.7
337	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	unit 818	Negative	0
338	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	unit 818	Negative	0
339	DOOR	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	SECOND	BATHROOM	unit 818	Negative	0
340	DOOR FRAME	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	SECOND	BATHROOM	unit 818	Negative	0
341	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 818	Negative	0
342	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 818	Negative	0

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
343	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 818	Negative	0
344	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 818	Negative	0
345	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 818	Negative	0
346	WINDOW FRAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 818	Negative	0
347	DOOR	WOOD	C	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 818	Negative	0
348	DOOR FRAME	WOOD	C	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 3	unit 818	Negative	0
349	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 818	Negative	0
350	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 818	Negative	0
351	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 818	Negative	0
352	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 818	Negative	0
353	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 818	Negative	0
354	WINDOW SIL	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	unit 818	Negative	0
355	RISER	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	SECOND	STAIR	unit 818	Negative	0.01
356	HAND RAIL	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	SECOND	STAIR	unit 818	Negative	0
357	CEILING	DRYWALL		INTACT	White	CEDAR GROVE 1	SECOND	STAIR	UNIT 806	Negative	0
358	WALL	DRYWALL	A	INTACT	White	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 806	Negative	0
359	WALL	DRYWALL	B	INTACT	White	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 806	Negative	0
360	WALL	DRYWALL	C	INTACT	White	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 806	Negative	0
361	WALL	DRYWALL	D	INTACT	White	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 806	Negative	0

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
362	DOOR	METAL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 806	Negative	0
363	DOOR FRAME	WOOD	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 806	Negative	0
364	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 806	Negative	0.14
365	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 806	Negative	0.08
366	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 806	Negative	0.5
367	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 806	Negative	0.04
368	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 806	Negative	0.05
369	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	UNIT 806	Negative	0.05
370	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	UNIT 806	Negative	0.5
371	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	UNIT 806	Negative	0.09
372	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	UNIT 806	Negative	0.08
373	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	UNIT 806	Negative	0.07
374	DOOR	WOOD	D	INTACT	BROWN	CEDAR GROVE 1	SECOND	BATHROOM	UNIT 806	Negative	0
375	DOOR FRAME	WOOD	D	INTACT	BROWN	CEDAR GROVE 1	SECOND	BATHROOM	UNIT 806	Negative	0
376	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	UNIT 806	Negative	0.4
377	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	UNIT 806	Negative	0.14
378	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	UNIT 806	Negative	0.6
379	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	UNIT 806	Negative	0.04
380	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	UNIT 806	Negative	0

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
381	WINDOW SILL	WOOD	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	UNIT 806	Negative	0
382	DOOR	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 1	UNIT 806	Negative	0
383	DOOR FRAME	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 1	UNIT 806	Negative	0
384	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	UNIT 806	Negative	0
385	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	UNIT 806	Negative	0
386	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	UNIT 806	Negative	0
387	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	UNIT 806	Negative	0
388	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	UNIT 806	Negative	0
389	NOT USED										
390	NOT USED										
391	NOT USED										
392	NOT USED										
393	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	UNIT 806	Negative	0
394	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	UNIT 806	Negative	0.6
395	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	UNIT 806	Negative	0
396	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	UNIT 806	Negative	0
397	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	UNIT 806	Negative	0.01
398	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	UNIT 806	Negative	0
399	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	UNIT 806	Negative	0

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
400	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	UNIT 806	Negative	0
401	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	UNIT 806	Negative	0
402	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	UNIT 806	Negative	0.07
403	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	UNIT 806	Negative	0
404	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	UNIT 806	Negative	0
405	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	UNIT 806	Negative	0.06
406	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	UNIT 806	Negative	0.01
407	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 4	UNIT 806	Negative	0.07
408	RISER	WOOD	D	INTACT	BROWN	CEDAR GROVE 1	SECOND	STAIR	UNIT 806	Negative	0.02
409	HAND RAIL	WOOD	D	INTACT	BROWN	CEDAR GROVE 1	SECOND	STAIR	UNIT 806	Negative	0
410	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	STAIR	UNIT 802	Negative	0
411	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	GARAGE	UNIT 802	Negative	0
412	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	GARAGE	UNIT 802	Negative	0
413	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	GARAGE	UNIT 802	Negative	0
414	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	GARAGE	UNIT 802	Negative	0
415	DOOR	METAL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	GARAGE	UNIT 802	Negative	0
416	DOOR	METAL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	GARAGE	UNIT 802	Negative	0
417	DOOR FRAME	METAL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	GARAGE	UNIT 802	Negative	0
418	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 804	Negative	0.02

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
419	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 804	Negative	0.01
420	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 804	Negative	0
421	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 804	Negative	0.1
422	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 804	Negative	0.06
423	SLIDING DOOR FRAME	WOOD	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 804	Negative	0
424	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 804	Negative	0
425	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 804	Negative	0
426	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 804	Negative	0
427	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 804	Negative	0
428	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 804	Negative	0
429	DOOR	METAL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 804	Negative	0
430	WINDOW SILL	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 804	Negative	0
431	WINDOW SILL	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 804	Negative	0
432	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	UNIT 804	Negative	0
433	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	UNIT 804	Negative	0
434	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	UNIT 804	Negative	0
435	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	UNIT 804	Negative	0
436	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	UNIT 804	Negative	0
437	WINDOW SIL	WOOD	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	UNIT 804	Negative	0

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
438	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	UNIT 804	Negative	0
439	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	UNIT 804	Negative	0
440	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	UNIT 804	Negative	0
441	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	UNIT 804	Negative	0
442	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	UNIT 804	Negative	0
443	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	UNIT 804	Negative	0
444	DOOR	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDOM 2	UNIT 804	Negative	0
445	DOOR FRAME	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDOM 2	UNIT 804	Negative	0
446	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	UNIT 804	Negative	0.04
447	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	UNIT 804	Negative	0.05
448	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	UNIT 804	Negative	0.04
449	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	UNIT 804	Negative	0.7
450	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	UNIT 804	Negative	0.5
451	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	UNIT 804	Negative	0
452	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	UNIT 804	Negative	0.02
453	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	UNIT 804	Negative	0
454	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	UNIT 804	Negative	0
455	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	UNIT 804	Negative	0
456	WINDOW SILL	WOOD	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	UNIT 804	Negative	0

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
457	DOOR	WOOD	B	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 3	UNIT 804	Negative	0
458	DOOR FRAME	WOOD	B	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 3	UNIT 804	Negative	0
459	TREAD	WOOD	B	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 3	UNIT 804	Negative	0
460	HAND RAIL	WOOD	B	INTACT	BROWN	CEDAR GROVE 1	SECOND	STAIR	UNIT 804	Negative	0
461	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 822	Negative	0.01
462	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 822	Negative	0.06
463	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 822	Negative	0.6
464	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 822	Negative	0.04
465	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 822	Negative	0.5
466	WALLSLIDING DOR FRAME	WOOD	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 822	Negative	0
467	WINDOW FRAME	WOOD	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 822	Negative	0
468	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 822	Negative	0
469	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 822	Negative	0
470	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 822	Negative	0.5
471	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 822	Negative	0
472	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 822	Negative	0
473	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 822	Negative	0
474	DOOR	METAL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 822	Negative	0
475	DOOR FRAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 822	Negative	0

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
476	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	UNIT 822	Negative	0
477	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	UNIT 822	Negative	0
478	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	UNIT 822	Negative	0
479	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	UNIT 822	Negative	0
480	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	UNIT 822	Negative	0
481	WINDOW FRAME	WOOD	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 1	UNIT 822	Negative	0
482	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	UNIT 822	Negative	0
483	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	UNIT 822	Negative	0
484	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	UNIT 822	Negative	0.6
485	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	UNIT 822	Negative	0
486	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BATHROOM	UNIT 822	Negative	0
487	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	UNIT 822	Negative	0
488	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	UNIT 822	Negative	0
489	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	UNIT 822	Negative	0
490	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	UNIT 822	Negative	0
491	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 2	UNIT 822	Negative	0
492	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	UNIT 822	Negative	0
493	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	UNIT 822	Negative	0
494	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	UNIT 822	Negative	0

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
495	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	UNIT 822	Negative	0
496	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	UNIT 822	Negative	0
497	WINDOW SILL	WOOD	C	INTACT	WHITE	CEDAR GROVE 1	SECOND	BEDROOM 3	UNIT 822	Negative	0
498	DOOR FRAME	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	SECOND	BEDROOM 3	UNIT 822	Negative	0
499	RISER	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	SECOND	STAIR	UNIT 822	Negative	0
500	HAND RAIL	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	SECOND	STAIR	UNIT 822	Negative	0

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
1	SHUTTER CAL										6.43
2	NIST STANDARD	PAINT			RED					Negative	0.9
3	NIST STANDARD	PAINT			RED					Positive	1
4	NIST STANDARD	PAINT			RED					Positive	1.3
5	NIST STANDARD	PAINT			RED					Positive	1
6	WALL	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	FIRST	MULTIPURPOSE ROOM	UNIT 802	Negative	< LOD
7	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	MULTIPURPOSE ROOM	UNIT 802	Negative	< LOD
8	WALL	WOOD	C	INTACT	BROWN	CEDAR GROVE 1	FIRST	MULTIPURPOSE ROOM	UNIT 802	Negative	< LOD
9	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	MULTIPURPOSE ROOM	UNIT 802	Negative	< LOD
10	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	FIRST	MULTIPURPOSE ROOM	UNIT 802	Negative	< LOD
11	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 802	Negative	< LOD
12	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 802	Negative	< LOD
13	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 802	Negative	< LOD
14	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 802	Negative	< LOD
15	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 802	Negative	< LOD
16	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM MEN	UNIT 802	Negative	< LOD
17	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM MEN	UNIT 802	Negative	< LOD
18	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM MEN	UNIT 802	Negative	< LOD
19	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM MEN	UNIT 802	Negative	< LOD
20	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM MEN	UNIT 802	Negative	< LOD

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
21	DOOR	WOOD	C	INTACT	BROWN	CEDAR GROVE 1	FIRST	BATHROOM MEN	UNIT 802	Negative	< LOD
22	DOOR FRAME	WOOD	C	INTACT	BROWN	CEDAR GROVE 1	FIRST	BATHROOM MEN	UNIT 802	Negative	< LOD
23	DOOR FRAME	WOOD	C	INTACT	BROWN	CEDAR GROVE 1	FIRST	BATHROOM WOMEN	UNIT 802	Negative	< LOD
24	DOOR	WOOD	C	INTACT	BROWN	CEDAR GROVE 1	FIRST	BATHROOM WOMEN	UNIT 802	Negative	< LOD
25	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM WOMEN	UNIT 802	Negative	< LOD
26	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM WOMEN	UNIT 802	Negative	< LOD
27	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM WOMEN	UNIT 802	Negative	< LOD
28	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	FIRST	BATHROOM WOMEN	UNIT 802	Negative	< LOD
29	FENCE	WOOD	C	INTACT	BEIGE	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 804	Negative	< LOD
30	FENCE	WOOD	C	INTACT	BEIGE	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 806	Negative	< LOD
31	FENCE	WOOD	C	INTACT	BEIGE	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 810	Negative	< LOD
32	FENCE	WOOD	C	INTACT	BEIGE	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 812	Negative	< LOD
33	FENCE	WOOD	C	INTACT	BEIGE	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 814	Negative	< LOD
34	FENCE	WOOD	C	INTACT	BEIGE	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 816	Negative	< LOD
35	SHINGLE	WOOD	C	INTACT	BROWN	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 816	Negative	< LOD
36	SHINGLE	WOOD	A	INTACT	BROWN	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 822	Negative	< LOD
37	SHINGLE	WOOD	C	INTACT	BROWN	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 820	Negative	< LOD
38	SHINGLE	WOOD	C	INTACT	BROWN	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 814	Negative	< LOD
39	SHINGLE	WOOD	C	INTACT	BROWN	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 812	Negative	< LOD
40	SHINGLE	WOOD	C	INTACT	BROWN	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 810	Negative	< LOD

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
41	SHINGLE	WOOD	C	INTACT	BROWN	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 808	Negative	< LOD
42	SHINGLE	WOOD	C	INTACT	BROWN	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 808	Negative	< LOD
43	SHINGLE	WOOD	C	INTACT	BROWN	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 806	Negative	< LOD
44	DOOR FRAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 804	Negative	< LOD
45	DOOR FRAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 802	Negative	< LOD
46	DOOR FRAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 806	Negative	< LOD
47	DOOR FRAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 808	Negative	< LOD
48	DOOR FRAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 810	Negative	< LOD
49	DOOR FRAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 812	Negative	< LOD
50	DOOR FRAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 814	Negative	< LOD
51	DOOR FRAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 816	Negative	< LOD
52	DOOR FRAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 818	Negative	< LOD
53	SHUTTER CAL										6.17
54	DOOR FRAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	EXTRIOR	UNIT 820	Negative	0
55	DOOR FRAME	WOOD	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	EXTRIOR	UNIT 822	Negative	0
56	POLE	METAL		INTACT	GREEN	CEDAR GROVE 1	FIRST	EXTRIOR	PLAYGRO UND	Negative	0
57	POLE	METAL		INTACT	YELLOW	CEDAR GROVE 1	FIRST	EXTRIOR	PLAYGRO UND	Negative	0
58	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 816	Negative	0
59	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 816	Negative	0
60	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 816	Negative	0

Reading	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Location	Positive/ Negative	XRF Reading
61	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 816	Negative	0
62	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	KITCHEN	UNIT 816	Negative	0.05
63	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 816	Negative	0.05
64	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 816	Negative	0.06
65	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 816	Negative	0
66	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 816	Negative	0
67	CEILING	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	LIVING ROOM	UNIT 816	Negative	0
68	CEILING	DRYWALL		INTACT	WHITE	CEDAR GROVE 1	FIRST	DIN ROOM	UNIT 816	Negative	0
69	WALL	DRYWALL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	DIN ROOM	UNIT 816	Negative	0
70	WALL	DRYWALL	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	DIN ROOM	UNIT 816	Negative	0
71	WALL	DRYWALL	C	INTACT	WHITE	CEDAR GROVE 1	FIRST	DIN ROOM	UNIT 816	Negative	0
72	WALL	DRYWALL	D	INTACT	WHITE	CEDAR GROVE 1	FIRST	DIN ROOM	UNIT 816	Negative	0
73	SLIDING DOOR FRAME	WOOD	B	INTACT	WHITE	CEDAR GROVE 1	FIRST	DIN ROOM	UNIT 816	Negative	0
74	DOOR	METAL	A	INTACT	WHITE	CEDAR GROVE 1	FIRST	EXTERIOR	UNIT 816	Negative	0

**TAB 2**  
**Certification**

---



**STATE OF WASHINGTON**

**Department of Commerce**  
Lead-Based Paint Program

**Janet J. Murphy**

*Has fulfilled the certification requirements of Washington Administrative code (WAC) 365-230 and has been certified to conduct lead-based paint activities pursuant to WAC 365-230-200 as a:*

**Risk Assessor**

<u>Certification #</u>	<u>Issuance Date</u>	<u>Expiration Date</u>
0258	3/23/2016	3/8/2019

**STATE OF WASHINGTON**

**Department of Commerce**

Lead-Based Paint Abatement Firm

**PBS Engineering & Environmental Inc.**

*Has fulfilled the certification requirements of  
WAC 365-230  
and has been certified to conduct lead-based  
paint activities.*

**Certification #**

178

**Issuance Date**

05/24/2017

**Expiration Date**

09/03/2019