Lead-Based Paint Inspection Report

Casa Madrona
3948 Martin Way East
Olympia, Washington 98506

Prepared for:
King County Housing Authority
700 Andover Park West
Seattle, Washington 98506

September 14, 2026
PBS Project KIN034 26012673

APEX
214 E GALER STREET, SUITE 300
SEATTLE, WA 98102
206.233.9639 MAIN
866.727.0140 FAX
PBSUSA.COM

LEAD-BASED PAINT INSPECTION REPORT

Casa Madrona
3948 Martin Way East
Olympia, Washington 98506

Prepared for:
King County Housing Authority
700 Andover Park West
Seattle, Washington 98188

Prepared by:
PBS Engineering and Environmental
214 E Galer Street, Suite 300
Seattle, WA 98102
(206) 233-9639

PBS Project KIN034 26012673
September 14, 2026

This report is for the exclusive use of the client for planned development of the property and is not to be relied upon by other parties. It is not to be photographed, photocopied, or similarly reproduced in total or in part without the expressed written consent of the client and PBS.

TABLE OF CONTENTS

1 IDENTIFYING INFORMATION 1

2 LEAD-BASED PAINT INSPECTION 2

2.1 Site Information 2

2.2 Lead-Based Paint Inspection and Sampling 2

2.2.1 XRF Sampling 2

2.2.2 Bulk Paint-Chip Sampling 3

Supporting Data

APPENDICES

Tab 1: XRF Data Sheets

Tab 2: Certifications

©2026 PBS Engineering and Environmental Inc.

1 IDENTIFYING INFORMATION

BUILDING DATA
Casa Madrona
3948 Martin Way East
Olympia, WA 98506

CLIENT DATA
King County Housing Authority (KCHA)
700 Andover Park West
Seattle, WA 98188

SCOPE OF ASSESSMENT

KCHA has requested that Apex Companies, LLC by and through its wholly owned subsidiary PBS Environmental LLC perform lead-based paint inspections at Casa Madrona Housing. PBS Apex conducted a lead-based paint inspection of 24 of the 70 Units at Casa Madrona on August 17th and 18th, 2026, in accordance with Chapter 7: Lead-Based Paint Inspection of the U.S. Department of Housing and Urban Development (HUD), Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing (HUD Guidelines).

CERTIFICATIONS

Lead Inspector/Risk Assessor
Janet Murphy
State of Washington Risk Assessor Certification No: 0258
Expiration Date: 03/08/2028

Janet Murphy
Signature

September 14, 2026
Date

Firm
PBS Engineering and Environmental
214 E Galer Street, Suite 300
Seattle, Washington 98102
Telephone: 206.223.9639

Certification No: 178
Expiration Date: 09/03/2025

2 LEAD-BASED PAINT INSPECTION

2.1 Site Information

Casa Madrona consists of one (1) building with a total of 70 units. This inspection was limited to 24 units by King County Housing. The buildings are of wood construction with gypsum wallboard interior walls and ceilings. The exterior siding and trim are cement board. Units are one, bedrooms with a bathroom, kitchen/living room area and a balcony. The buildings are in good condition. There are not common areas present in the buildings.

Architectural finishes are uniform throughout. The majority of the interior components are painted. Walls are painted gypsum wallboard. Windows in units have wood or gypsum board sills. The doors and door frames are painted wood. The window frames are aluminum with painted wood trim. Cove base is vinyl.

2.2 Lead-Based Paint Inspection and Sampling

Based on a review of King County Assessor records, Casa Madrona was constructed in 1968.

2.2.1 XRF Sampling

The presence of lead in paint was determined through x-ray fluorescence spectroscopy. A handheld Niton Inc. X-Ray Fluorescence (XRF) Analyzer, Model XLP 300A Version 5.2.1 P/N 500-926 Serial #102877 operating in lead paint mode was used to perform a surface-by-surface lead paint inspection of each painted surface in the selected units and other building areas. Calibration was checked based on the requirements of the Performance Characteristic Sheet for the XRF Analyzer. All calibration readings were within the tolerance for this instrument. No substrate correction is required with this instrument.

HUD and the U.S. Environmental Protection Agency (EPA) have set 1.0 milligrams per square centimeter (mg/cm^2) as the threshold limit for lead-based paint as determined through X-Ray Fluorescence (XRF) testing. HUD and EPA have set 5,000 parts per million (ppm) or 0.5% by atomic absorption spectroscopy (AAS) laboratory analysis as the threshold limit for lead-based paint. Paint that is known to contain lead levels less than those described above does not have to be evaluated, although all deteriorated paint (paint surfaces in poor condition) should be repaired because it may contain lower levels of lead that may contribute to lead dust or lead contaminated soil hazards.

The "Side" information presented on the XRF data sheets is in relation to the side of the rooms or building exteriors where the unit number is located. The inspector/risk assessor used the address side of each residence as the basis to establish side "A." Sides B, C, and D follow in clockwise rotation.

Please refer to the XRF Sample Data Table located in Tab 1 for a complete list of XRF samples.

2.2.2 Bulk Paint-Chip Sampling

Bulk paint chip verification samples are collected when there is an inconclusive result with the XRF. There were no inconclusive results with the XRF analyzer. No bulk paint chip samples were collected.

2.2.3 Components with Lead-Based Paint

Lead was **not** found in any of the paint on building components above the HUD lead-based paint threshold of 1.0 mg/cm^2 by XRF.

TAB 1

XRF Data Sheets

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
1		Shutter Cal						
2		NIST Standard				Yellow	Positive	1.1
3		Shutter Cal						
4		Shutter Cal						
5		Shutter Cal						
6		Shutter Cal						
7		Shutter Cal						
8		NIST Standard				Yellow	Positive	3.1
9	8/17/2026 10:39	Shutter Cal						
10	8/17/2026 10:52	NIST Standard	PAINT			YELLOW	Positive	1.4
11	8/17/2026 10:52	NIST Standard	PAINT			YELLOW	Positive	1.5
12	8/17/2026 10:53	NIST Standard	PAINT			YELLOW	Positive	1.5
13	8/17/2026 10:59	EXTERIOR WALL	STUCCO	Exterior A	INTACT	YELLOW	Negative	<LOD
14	8/17/2026 11:00	EXTERIOR WALL	STUCCO	Exterior B	INTACT	YELLOW	Negative	<LOD
15	8/17/2026 11:01	EXTERIOR WALL	STUCCO	Exterior C	INTACT	YELLOW	Negative	<LOD
16	8/17/2026 11:01	EXTERIOR WALL	STUCCO	Exterior D	INTACT	YELLOW	Negative	<LOD
17	8/17/2026 11:02	EXTERIOR WALL	STUCCO	Exterior A	INTACT	YELLOW	Negative	<LOD
18	8/17/2026 11:04	EXTERIOR TRIM	WOOD	Exterior A	INTACT	BROWN	Negative	<LOD
19	8/17/2026 11:04	EXTERIOR TRIM	WOOD	Exterior B	INTACT	BROWN	Negative	<LOD
20	8/17/2026 11:05	EXTERIOR TRIM	WOOD	Exterior C	INTACT	BROWN	Negative	<LOD
21	8/17/2026 11:06	EXTERIOR TRIM	WOOD	Exterior D	INTACT	BROWN	Negative	<LOD
22	8/17/2026 11:07	EXTERIOR DOOR	METAL	Exterior A	INTACT	BROWN	Negative	<LOD
23	8/17/2026 11:08	EXTERIOR DOOR	METAL	Exterior B	INTACT	BROWN	Negative	<LOD
24	8/17/2026 11:09	EXTERIOR DOOR	METAL	Exterior C	INTACT	BROWN	Negative	<LOD
25	8/17/2026 11:09	EXTERIOR DOOR	METAL	Exterior D	INTACT	BROWN	Negative	<LOD
26	8/17/2026 11:19	CEILING	DRYWALL	1st Floor Hall	INTACT	WHITE	Negative	<LOD
27	8/17/2026 11:20	WALL	DRYWALL	1st Floor Hall Side A	INTACT	WHITE	Negative	<LOD
28	8/17/2026 11:21	WALL	DRYWALL	1st Floor Hall Side B	INTACT	WHITE	Negative	<LOD
29	8/17/2026 11:22	WALL	DRYWALL	1st Floor Hall Side C	INTACT	WHITE	Negative	<LOD
30	8/17/2026 11:23	WALL	DRYWALL	1st Floor Hall Side D	INTACT	YELLOW	Negative	<LOD
31	8/17/2026 11:25	WALL	DRYWALL	1st Floor Hall Side A	INTACT	YELLOW	Negative	<LOD
32	8/17/2026 11:26	WALL	DRYWALL	1st Floor Hall Side B	INTACT	YELLOW	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
33	8/17/2026 11:26	WALL	DRYWALL	1st Floor Hall Side C	INTACT	YELLOW	Negative	<LOD
34	8/17/2026 11:29	WALL	DRYWALL	1st Floor Hall Side D	INTACT	GREEN	Negative	<LOD
35	8/17/2026 11:29	WALL	DRYWALL	2nd Floor Hall Side A	INTACT	GREEN	Negative	<LOD
36	8/17/2026 11:30	WALL	DRYWALL	2nd Floor Hall Side C	INTACT	GREEN	Negative	<LOD
37	8/17/2026 11:41	CEILING	DRYWALL	Unit 101 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
38	8/17/2026 11:42	WALL	DRYWALL	Unit 101 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
39	8/17/2026 11:43	WALL	DRYWALL	Unit 101 Kitchen/Living Room B	INTACT	WHITE	Negative	<LOD
40	8/17/2026 11:44	WALL	DRYWALL	Unit 101 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
41	8/17/2026 11:45	WALL	DRYWALL	Unit 101 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
42	8/17/2026 11:46	CEILING	DRYWALL	Unit 101 Bathroom	INTACT	WHITE	Negative	<LOD
43	8/17/2026 11:48	WALL	DRYWALL	Unit 101 Bathroom A	INTACT	WHITE	Negative	<LOD
44	8/17/2026 11:49	WALL	DRYWALL	Unit 101 Bathroom B	INTACT	WHITE	Negative	<LOD
45	8/17/2026 11:50	WALL	DRYWALL	Unit 101 Bathroom C	INTACT	WHITE	Negative	<LOD
46	8/17/2026 11:51	WALL	DRYWALL	Unit 101 Bathroom D	INTACT	WHITE	Negative	<LOD
47	8/17/2026 11:51	DOOR	WOOD	Unit 101 Bathroom D	INTACT	WHITE	Negative	<LOD
48	8/17/2026 11:52	DOOR FRAME	WOOD	Unit 101 Bathroom D	INTACT	WHITE	Negative	<LOD
49	8/17/2026 11:54	CEILING	DRYWALL	Unit 101 Bedroom	INTACT	WHITE	Negative	<LOD
50	8/17/2026 11:54	WALL	DRYWALL	Unit 101 Bedroom A	INTACT	WHITE	Negative	<LOD
51	8/17/2026 11:55	WALL	DRYWALL	Unit 101 Bedroom B	INTACT	WHITE	Negative	<LOD
52	8/17/2026 11:56	WALL	DRYWALL	Unit 101 Bedroom C	INTACT	WHITE	Negative	<LOD
53	8/17/2026 11:57	WALL	DRYWALL	Unit 101 Bedroom D	INTACT	WHITE	Negative	<LOD
54	8/17/2026 11:57	WALL	DRYWALL	Unit 101 Bedroom A	INTACT	WHITE	Negative	<LOD
55	8/17/2026 11:58	WINDOW SILL	WOOD	Unit 101 Bedroom C	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
56	8/17/2026 11:59	WINDOW FRAME	WOOD	Unit 101 Bedroom C	INTACT	WHITE	Negative	<LOD
57	8/17/2026 12:00	DOOR	WOOD	Unit 101 Bedroom Door B	INTACT	WHITE	Negative	<LOD
58	8/17/2026 12:01	DOOR FRAME	WOOD	Unit 101 Bedroom Door Frame B	INTACT	WHITE	Negative	<LOD
59	8/17/2026 12:02	DOOR	WOOD	Unit 101 A	INTACT	WHITE	Negative	<LOD
60	8/17/2026 12:05	DOOR FRAME	WOOD	Unit 101 A	INTACT	BEIGE	Negative	<LOD
61	8/17/2026 12:06	DOOR FRAME	WOOD	Unit 102	INTACT	BEIGE	Negative	<LOD
62	8/17/2026 12:08	DOOR	WOOD	Unit 102	INTACT	WHITE	Negative	<LOD
63	8/17/2026 12:09	CEILING	DRYWALL	Unit 102 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
64	8/17/2026 12:10	WALL	DRYWALL	Unit 102 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
65	8/17/2026 12:11	WALL	DRYWALL	Unit 102 Kitchen/Living Room B	INTACT	WHITE	Negative	<LOD
66	8/17/2026 12:12	WALL	DRYWALL	Unit 102 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
67	8/17/2026 12:13	WALL	DRYWALL	Unit 102 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
68	8/17/2026 12:14	SILL	WOOD	Unit 102 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
69	8/17/2026 12:15	CEILING	DRYWALL	Unit 102 Bedroom	INTACT	WHITE	Negative	<LOD
70	8/17/2026 12:16	WALL	DRYWALL	UNIT 102 Bedroom A	INTACT	WHITE	Negative	<LOD
71	8/17/2026 12:17	WALL	DRYWALL	UNIT 102 Bedroom B	INTACT	WHITE	Negative	<LOD
72	8/17/2026 12:17	WALL	DRYWALL	UNIT 102 Bedroom C	INTACT	WHITE	Negative	<LOD
73	8/17/2026 12:19	WINDOW SILL	WOOD	UNIT 102 Bedroom C	INTACT	WHITE	Negative	<LOD
74	8/17/2026 12:19	WINDOW FRAME	WOOD	UNIT 102 Bedroom C	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
75	8/17/2026 12:20	DOOR	WOOD	UNIT 102 Bedroom A	INTACT	WHITE	Negative	<LOD
76	8/17/2026 12:21	DOOR FRAME	WOOD	UNIT 102 Bedroom A	INTACT	WHITE	Negative	<LOD
77	8/17/2026 12:23	CEILING	DRYWALL	UNIT 102 Bathroom	INTACT	WHITE	Negative	<LOD
78	8/17/2026 12:24	WALL	DRYWALL	Unit 102 Bathroom A	INTACT	WHITE	Negative	<LOD
79	8/17/2026 12:25	WALL	DRYWALL	Unit 102 Bathroom B	INTACT	WHITE	Negative	<LOD
80	8/17/2026 12:25	WALL	DRYWALL	Unit 102 Bathroom C	INTACT	WHITE	Negative	<LOD
81	8/17/2026 12:26	WALL	DRYWALL	Unit 102 Bathroom D	INTACT	WHITE	Negative	<LOD
82	8/17/2026 12:26	WALL	DRYWALL	Unit 102 Bathroom D	INTACT	WHITE	Negative	<LOD
83	8/17/2026 12:27	DOOR	WOOD	Unit 102 Bathroom D	INTACT	WHITE	Negative	<LOD
84	8/17/2026 12:28	DOOR FRAME	WOOD	Unit 102 Bathroom D	INTACT	WHITE	Negative	<LOD
85	8/17/2026 12:39	DOOR	WOOD	UNIT 103	INTACT	WHITE	Negative	<LOD
86	8/17/2026 12:40	DOOR FRAME	WOOD	UNIT 103	INTACT	BEIGE	Negative	<LOD
87	8/17/2026 12:42	CEILING	DRYWALL	Unit 103 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
88	8/17/2026 12:43	DOOR	WOOD	Unit 103 Kitchen/Living Room	INTACT	GREEN	Negative	<LOD
89	8/17/2026 12:43	WALL	DRYWALL	Unit 103 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
90	8/17/2026 12:44	WALL	DRYWALL	Unit 103 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
91	8/17/2026 12:45	WALL	DRYWALL	Unit 103 Kitchen/Living Room B	INTACT	WHITE	Negative	<LOD
92	8/17/2026 12:46	WALL	DRYWALL	Unit 103 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
93	8/17/2026 12:48	WINDOW SILL	WOOD	Unit 103 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
94	8/17/2026 12:49	WINDOW FRAME	WOOD	Unit 103 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
95	8/17/2026 12:50	CEILING	DRYWALL	Unit 103 Bedroom	INTACT	WHITE	Negative	<LOD
96	8/17/2026 12:52	WALL	DRYWALL	Unit 103 Bedroom A	INTACT	WHITE	Negative	<LOD
97	8/17/2026 12:53	WALL	DRYWALL	Unit 103 Bedroom B	INTACT	WHITE	Negative	<LOD
98	8/17/2026 12:53	WALL	DRYWALL	Unit 103 Bedroom C	INTACT	WHITE	Negative	<LOD
99	8/17/2026 12:54	WALL	DRYWALL	Unit 103 Bedroom D	INTACT	WHITE	Negative	<LOD
100	8/17/2026 12:55	DOOR	WOOD	Unit 103 Bedroom D	INTACT	WHITE	Negative	<LOD
101	8/17/2026 12:55	DOOR FRAME	WOOD	Unit 103 Bedroom D	INTACT	WHITE	Negative	<LOD
102	8/17/2026 12:57	CEILING	DRYWALL	UNIT 103 Bathroom	INTACT	WHITE	Negative	<LOD
103	8/17/2026 12:58	CEILING	DRYWALL	UNIT 103 Bathroom	INTACT	WHITE	Negative	<LOD
104	8/17/2026 12:58	CEILING	DRYWALL	UNIT 103 Bathroom	INTACT	WHITE	Negative	<LOD
105	8/17/2026 12:59	CEILING	DRYWALL	UNIT 103 Bathroom	INTACT	WHITE	Negative	<LOD
106	8/17/2026 12:59	CEILING	DRYWALL	UNIT 103 Bathroom	INTACT	WHITE	Negative	<LOD
107	8/17/2026 13:00	WALL	DRYWALL	UNIT 103 Bathroom A	INTACT	WHITE	Negative	<LOD
108	8/17/2026 13:01	WALL	DRYWALL	UNIT 103 Bathroom B	INTACT	WHITE	Negative	<LOD
109	8/17/2026 13:02	WALL	DRYWALL	UNIT 103 Bathroom C	INTACT	WHITE	Negative	<LOD
110	8/17/2026 13:02	WALL	DRYWALL	UNIT 103 Bathroom D	INTACT	WHITE	Negative	<LOD
111	8/17/2026 13:03	WALL	DRYWALL	UNIT 103 Bathroom D	INTACT	WHITE	Negative	<LOD
112	8/17/2026 13:04	DOOR	WOOD	UNIT 103 Bathroom D	INTACT	WHITE	Negative	<LOD
113	8/17/2026 13:04	DOOR FRAME	WOOD	UNIT 103 Bathroom D	INTACT	WHITE	Negative	<LOD
114	8/17/2026 13:07	CEILING	DRYWALL	Unit 106 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
115	8/17/2026 13:08	WALL	DRYWALL	Unit 106 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
116	8/17/2026 13:09	WALL	DRYWALL	Unit 106 Kitchen/Living Room B	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
117	8/17/2026 13:10	WALL	DRYWALL	Unit 106 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
118	8/17/2026 13:10	WALL	DRYWALL	Unit 106 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
119	8/17/2026 13:12	WINDOW SILL	WOOD	Unit 106 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
120	8/17/2026 13:13	WINDOW SILL	WOOD	Unit 106 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
121	8/17/2026 13:13	WINDOW FRAME	WOOD	Unit 106 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
122	8/17/2026 13:15	CEILING	DRYWALL	UNIT 106 Bathroom	INTACT	WHITE	Negative	<LOD
123	8/17/2026 13:15	CEILING	DRYWALL	UNIT 106 Bathroom	INTACT	WHITE	Negative	<LOD
124	8/17/2026 13:17	WALL	DRYWALL	UNIT 106 Bathroom A	INTACT	WHITE	Negative	<LOD
125	8/17/2026 13:17	WALL	DRYWALL	UNIT 106 Bathroom B	INTACT	WHITE	Negative	<LOD
126	8/17/2026 13:19	WALL	DRYWALL	UNIT 106 Bathroom C	INTACT	WHITE	Negative	<LOD
127	8/17/2026 13:19	WALL	DRYWALL	UNIT 106 Bathroom D	INTACT	WHITE	Negative	<LOD
128	8/17/2026 13:19	WALL	DRYWALL	UNIT 106 Bathroom C	INTACT	WHITE	Negative	<LOD
129	8/17/2026 13:20	DOOR	WOOD	UNIT 106 Bathroom D	INTACT	WHITE	Negative	<LOD
130	8/17/2026 13:21	DOOR	WOOD	UNIT 106 Bathroom D	INTACT	WHITE	Negative	<LOD
131	8/17/2026 13:22	DOOR FRAME	WOOD	UNIT 106 Bathroom D	INTACT	WHITE	Negative	<LOD
132	8/17/2026 13:23	CEILING	DRYWALL	UNIT 106 Bedroom	INTACT	WHITE	Negative	<LOD
133	8/17/2026 13:24	WALL	DRYWALL	UNIT 106 Bedroom A	INTACT	WHITE	Negative	<LOD
134	8/17/2026 13:26	WALL	DRYWALL	UNIT 106 Bedroom B	INTACT	WHITE	Negative	<LOD
135	8/17/2026 13:26	WALL	DRYWALL	UNIT 106 Bedroom C	INTACT	WHITE	Negative	<LOD
136	8/17/2026 13:27	WALL	DRYWALL	UNIT 106 Bedroom C	INTACT	WHITE	Negative	<LOD
137	8/17/2026 13:28	WALL	DRYWALL	UNIT 106 Bedroom D	INTACT	WHITE	Negative	<LOD
138	8/17/2026 13:29	WINDOW SILL	WOOD	UNIT 106 Bedroom	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
139	8/17/2026 13:30	WINDOW FRAME	WOOD	UNIT 106 Bedroom	INTACT	WHITE	Negative	<LOD
140	8/17/2026 13:30	DOOR	WOOD	UNIT 106 Bedroom	INTACT	WHITE	Negative	<LOD
141	8/17/2026 13:31	DOOR FRAME	WOOD	UNIT 106 Bedroom	INTACT	WHITE	Negative	<LOD
142	8/17/2026 13:36	DOOR	WOOD	UNIT 113 Front Door A	INTACT	GREEN	Negative	<LOD
143	8/17/2026 13:37	DOOR FRAME	WOOD	UNIT 113 Front Door A	INTACT	BEIGE	Negative	<LOD
144	8/17/2026 13:37	DOOR FRAME	WOOD	UNIT 113 Front Door A	INTACT	BEIGE	Negative	<LOD
145	8/17/2026 13:38	CEILING	DRYWALL	Unit 113 Kitchen/Living Room	INTACT	BEIGE	Negative	<LOD
146	8/17/2026 13:39	WALL	DRYWALL	Unit 113 Kitchen/Living Room A	INTACT	BEIGE	Negative	<LOD
147	8/17/2026 13:40	WALL	DRYWALL	Unit 113 Kitchen/Living Room B	INTACT	BEIGE	Negative	<LOD
148	8/17/2026 13:41	WALL	DRYWALL	Unit 113 Kitchen/Living Room C	INTACT	BEIGE	Negative	<LOD
149	8/17/2026 13:42	WALL	DRYWALL	Unit 113 Kitchen/Living Room D	INTACT	BEIGE	Negative	<LOD
150	8/17/2026 13:43	WINDOW SILL	WOOD	Unit 113 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
151	8/17/2026 13:44	WINDOW FAME	WOOD	Unit 113 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
152	8/17/2026 13:46	CEILING	DRYWALL	UNIT 113 Bedroom	INTACT	WHITE	Negative	<LOD
153	8/17/2026 13:47	WALL	DRYWALL	UNIT 113 Bedroom A	INTACT	WHITE	Negative	<LOD
154	8/17/2026 13:47	WALL	DRYWALL	UNIT 113 Bedroom B	INTACT	WHITE	Negative	<LOD
155	8/17/2026 13:48	WALL	DRYWALL	UNIT 113 Bedroom C	INTACT	WHITE	Negative	<LOD
156	8/17/2026 13:49	WALL	DRYWALL	UNIT 113 Bedroom D	INTACT	WHITE	Negative	<LOD
157	8/17/2026 13:50	DOOR	WOOD	UNIT 113 Bedroom D	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
158	8/17/2026 13:51	DOOR FRAME	WOOD	UNIT 113 Bedroom D	INTACT	WHITE	Negative	<LOD
159	8/17/2026 13:51	DOOR FRAME	WOOD	UNIT 113 Bedroom D	INTACT	WHITE	Negative	<LOD
160	8/17/2026 13:52	CEILING	DRYWALL	UNIT 113 Bathroom	INTACT	WHITE	Negative	<LOD
161	8/17/2026 13:53	CEILING	DRYWALL	UNIT 113 Bathroom	INTACT	WHITE	Negative	<LOD
162	8/17/2026 13:54	WALL	DRYWALL	UNIT 113 Bathroom A	INTACT	WHITE	Negative	<LOD
163	8/17/2026 13:54	WALL	DRYWALL	UNIT 113 Bathroom A	INTACT	WHITE	Negative	<LOD
164	8/17/2026 13:56	WALL	DRYWALL	Unit 113 Bathroom B	INTACT	WHITE	Negative	<LOD
165	8/17/2026 13:56	WALL	DRYWALL	Unit 113 Bathroom C	INTACT	WHITE	Negative	<LOD
166	8/17/2026 13:57	WALL	DRYWALL	Unit 113 Bathroom D	INTACT	WHITE	Negative	<LOD
167	8/17/2026 13:58	DOOR	WOOD	Unit 113 Bathroom C	INTACT	WHITE	Negative	<LOD
168	8/17/2026 13:59	DOOR	WOOD	Un it 113 Bathroom C	INTACT	WHITE	Negative	<LOD
169	8/17/2026 13:59	DOOR FRAME	WOOD	Unit 113 Bathroom C	INTACT	WHITE	Negative	<LOD
170	8/17/2026 15:10	Shutter Cal						
171	8/17/2026 15:22	Shutter Cal						
172	8/17/2026 15:32	Shutter Cal						
173	8/17/2026 15:34	Shutter Cal						
174	8/17/2026 15:35	NIST Standard				Yellow	Positive	1.5
175	8/17/2026 15:35	NIST Standard				Yellow	Positive	1.5
176	8/17/2026 15:36	NIST Standard				Yellow	Positive	1.3
177	8/17/2026 15:42	CEILING	DRYWALL	Unit 110 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
178	8/17/2026 15:43	WALL	DRYWALL	Unit 110 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
179	8/17/2026 15:44	WALL	DRYWALL	Unit 110 Kitchen/Living Room B	INTACT	WHITE	Negative	<LOD
180	8/17/2026 15:45	WALL	DRYWALL	Unit 110 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
181	8/17/2026 15:46	WALL	DRYWALL	Unit 110 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
182	8/17/2026 15:47	DOOR	WOOD	Unit 110 Kitchen/Living Room A	INTACT	GREEN	Negative	<LOD
183	8/17/2026 15:48	DOOR FRAME	WOOD	Unit 110 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
184	8/17/2026 15:49	WINDOW FRAME	WOOD	Unit 110 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
185	8/17/2026 15:49	WINDOW SILL	WOOD	Unit 110 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
186	8/17/2026 15:51	CEILING	DRYWALL	UNIT 110 Bedroom	INTACT	WHITE	Negative	<LOD
187	8/17/2026 15:52	WALL	DRYWALL	UNIT 110 Bedroom A	INTACT	WHITE	Negative	<LOD
188	8/17/2026 15:53	WALL	DRYWALL	UNIT 110 Bedroom B	INTACT	WHITE	Negative	<LOD
189	8/17/2026 15:53	WALL	DRYWALL	UNIT 110 Bedroom C	INTACT	WHITE	Negative	<LOD
190	8/17/2026 15:54	WALL	DRYWALL	UNIT 110 Bedroom D	INTACT	WHITE	Negative	<LOD
191	8/17/2026 15:54	WALL	DRYWALL	UNIT 110 Bedroom D	INTACT	WHITE	Negative	<LOD
192	8/17/2026 15:55	DOOR	WOOD	UNIT 110 Bedroom A	INTACT	WHITE	Negative	<LOD
193	8/17/2026 15:56	DOOR FRAME	WOOD	UNIT 110 Bedroom A	INTACT	WHITE	Negative	<LOD
194	8/17/2026 15:57	WINDOW SILL	WOOD	UNIT 110 Bedroom C	INTACT	WHITE	Negative	<LOD
195	8/17/2026 15:58	WINDOW FRAME	WOOD	UNIT 110 Bedroom C	INTACT	WHITE	Negative	<LOD
196	8/17/2026 15:59	CEILING	DRYWALL	UNIT 110 Bathroom D	INTACT	WHITE	Negative	<LOD
197	8/17/2026 16:00	WALL	DRYWALL	UNIT 110 Bathroom D	INTACT	WHITE	Negative	<LOD
198	8/17/2026 16:01	WALL	DRYWALL	UNIT 110 Bathroom B	INTACT	WHITE	Negative	<LOD
199	8/17/2026 16:01	WALL	DRYWALL	UNIT 110 Bathroom C	INTACT	WHITE	Negative	<LOD
200	8/17/2026 16:02	DOOR	WOOD	UNIT 110 Bathroom D	INTACT	WHITE	Negative	<LOD
201	8/17/2026 16:03	DOOR FRAME	WOOD	UNIT 110 Bathroom D	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
202	8/17/2026 16:05	CEILING	DRYWALL	Unit 111 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
203	8/17/2026 16:06	WALL	DRYWALL	Unit 111 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
204	8/17/2026 16:07	WALL	DRYWALL	Unit 111 Kitchen/Living Room B	INTACT	WHITE	Negative	<LOD
205	8/17/2026 16:08	WALL	DRYWALL	Unit 111 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
206	8/17/2026 16:09	WALL	DRYWALL	Unit 111 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
207	8/17/2026 16:10	window sill	WOOD	Unit 111 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
208	8/17/2026 16:11	window frame	WOOD	Unit 111 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
209	8/17/2026 16:12	CEILING	DRYWALL	UNIT 111 Bedroom	INTACT	WHITE	Negative	<LOD
210	8/17/2026 16:13	WALL	DRYWALL	UNIT 111 Bedroom A	INTACT	WHITE	Negative	<LOD
211	8/17/2026 16:14	WALL	DRYWALL	UNIT 111 Bedroom B	INTACT	WHITE	Negative	<LOD
212	8/17/2026 16:14	WALL	DRYWALL	UNIT 111 Bedroom C	INTACT	WHITE	Negative	<LOD
213	8/17/2026 16:15	WALL	DRYWALL	UNIT 111 Bedroom D	INTACT	WHITE	Negative	<LOD
214	8/17/2026 16:16	WINDOW SILL	WOOD	UNIT 111 Bedroom C	INTACT	WHITE	Negative	<LOD
215	8/17/2026 16:17	WINDOW FRAME	WOOD	UNIT 111 Bedroom C	INTACT	WHITE	Negative	<LOD
216	8/17/2026 16:18	DOOR	WOOD	UNIT 111 Bedroom D	INTACT	WHITE	Negative	<LOD
217	8/17/2026 16:18	DOOR FRAME	WOOD	UNIT 111 Bedroom D	INTACT	WHITE	Negative	<LOD
218	8/17/2026 16:20	CEILING	DRYWALL	UNIT 111 Bathroom	INTACT	WHITE	Negative	<LOD
219	8/17/2026 16:21	WALL	DRYWALL	UNIT 111 Bathroom A	INTACT	WHITE	Negative	<LOD
220	8/17/2026 16:22	WALL	DRYWALL	UNIT 111 Bathroom B	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
221	8/17/2026 16:22	WALL	DRYWALL	UNIT 111 Bathroom C	INTACT	WHITE	Negative	<LOD
222	8/17/2026 16:23	WALL	DRYWALL	UNIT 111 Bathroom D	INTACT	WHITE	Negative	<LOD
223	8/17/2026 16:24	DOOR	WOOD	UNIT 111 Bathroom D	INTACT	WHITE	Negative	<LOD
224	8/17/2026 16:24	DOOR FRAME	WOOD	UNIT 111 Bathroom D	INTACT	WHITE	Negative	<LOD
225	8/17/2026 16:26	CEILING	DRYWALL	Unit 116 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
226	8/17/2026 16:27	WALL	DRYWALL	Unit 116 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
227	8/17/2026 16:28	WALL	DRYWALL	Unit 116 Kitchen/Living Room B	INTACT	WHITE	Negative	<LOD
228	8/17/2026 16:29	WALL	DRYWALL	Unit 116 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
229	8/17/2026 16:30	WALL	DRYWALL	Unit 116 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
230	8/17/2026 16:32	WINDOW SILL	WOOD	Unit 116 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
231	8/17/2026 16:32	WINDOW FRAME	WOOD	Unit 116 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
232	8/17/2026 16:34	CEILING	DRYWALL	UNIT 116 Bedroom	INTACT	WHITE	Negative	<LOD
233	8/17/2026 16:35	WALL	DRYWALL	UNIT 116 Bedroom A	INTACT	WHITE	Negative	<LOD
234	8/17/2026 16:36	WALL	DRYWALL	UNIT 116 Bedroom B	INTACT	WHITE	Negative	<LOD
235	8/17/2026 16:37	WALL	DRYWALL	UNIT 116 Bedroom C	INTACT	WHITE	Negative	<LOD
236	8/17/2026 16:38	WALL	DRYWALL	UNIT 116 Bedroom D	INTACT	WHITE	Negative	<LOD
237	8/17/2026 16:39	WINDOW SILL	WOOD	UNIT 116 Bedroom C	INTACT	WHITE	Negative	<LOD
238	8/17/2026 16:40	WINDOW FRAME	WOOD	UNIT 116 Bedroom C	INTACT	WHITE	Negative	<LOD
239	8/17/2026 16:40	DOOR	WOOD	UNIT 116 Bedroom D	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
240	8/17/2026 16:41	DOOR FRAME	WOOD	UNIT 116 Bedroom D	INTACT	WHITE	Negative	<LOD
241	8/17/2026 16:42	CEILING	DRYWALL	UNIT 116 Bathroom	INTACT	WHITE	Negative	<LOD
242	8/17/2026 16:43	WALL	DRYWALL	UNIT 116 Bathroom A	INTACT	WHITE	Negative	0.01
243	8/17/2026 16:43	WALL	DRYWALL	UNIT 116 Bathroom B	INTACT	WHITE	Negative	0.01
244	8/17/2026 16:44	WALL	DRYWALL	UNIT 116 Bathroom C	INTACT	WHITE	Negative	<LOD
245	8/17/2026 16:45	WALL	DRYWALL	UNIT 116 Bathroom D	INTACT	WHITE	Negative	<LOD
246	8/17/2026 16:45	DOOR	WOOD	UNIT 116 Kitchen/Living Room A	INTACT	BEIGE	Negative	0.01
247	8/17/2026 16:46	DOOR FRAME	WOOD	UNIT 116 Kitchen/Living Room A	INTACT	BEIGE	Negative	0.01
248	8/17/2026 16:47	DOOR	WOOD	UNIT 116 Bathroom D	INTACT	WHITE	Negative	<LOD
249	8/17/2026 16:48	DOOR FRAME	WOOD	UNIT 116 Bathroom D	INTACT	WHITE	Negative	<LOD
250	8/17/2026 16:56	CEILING	DRYWALL	Unit 125 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
251	8/17/2026 16:57	WALL	DRYWALL	Unit 125 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
252	8/17/2026 16:58	WALL	DRYWALL	Unit 125 Kitchen/Living Room B	INTACT	WHITE	Negative	<LOD
253	8/17/2026 16:58	WALL	DRYWALL	Unit 125 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
254	8/17/2026 16:59	WALL	DRYWALL	Unit 125 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
255	8/17/2026 16:59	DOOR	WOOD	Unit 125 Kitchen/Living Room A	INTACT	BEIGE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
256	8/17/2026 17:00	DOOR FRAME	WOOD	Unit 125 Kitchen/Living Room A	INTACT	BEIGE	Negative	<LOD
257	8/17/2026 17:01	WINDOW SILL	WOOD	Unit 125 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
258	8/17/2026 17:02	WINDOW FRAME	WOOD	Unit 125 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
259	8/17/2026 17:04	CEILING	DRYWALL	UNIT 125 Bedroom	INTACT	WHITE	Negative	<LOD
260	8/17/2026 17:05	WALL	DRYWALL	UNIT 125 Bedroom A	INTACT	WHITE	Negative	<LOD
261	8/17/2026 17:06	WALL	DRYWALL	UNIT 125 Bedroom B	INTACT	WHITE	Negative	<LOD
262	8/17/2026 17:06	WALL	DRYWALL	UNIT 125 Bedroom C	INTACT	WHITE	Negative	<LOD
263	8/17/2026 17:07	WALL	DRYWALL	UNIT 125 Bedroom D	INTACT	WHITE	Negative	<LOD
264	8/17/2026 17:07	WALL	DRYWALL	UNIT 125 Bedroom D	INTACT	WHITE	Negative	<LOD
265	8/17/2026 17:08	WALL	DRYWALL	UNIT 125 Bedroom D	INTACT	WHITE	Negative	<LOD
266	8/17/2026 17:09	WINDOW SILL	WOOD	UNIT 125 Bedroom C	INTACT	WHITE	Negative	<LOD
267	8/17/2026 17:10	WINDOW FRAME	WOOD	UNIT 125 Bedroom C	INTACT	WHITE	Negative	<LOD
268	8/17/2026 17:10	DOOR	WOOD	UNIT 125 Bedroom D	INTACT	WHITE	Negative	<LOD
269	8/17/2026 17:11	DOOR FRAME	WOOD	UNIT 125 Bedroom D	INTACT	WHITE	Negative	<LOD
270	8/17/2026 17:13	CEILING	DRYWALL	UNIT 125 Bathroom	INTACT	WHITE	Negative	<LOD
271	8/17/2026 17:14	WALL	DRYWALL	UNIT 125 Bathroom A	INTACT	WHITE	Negative	<LOD
272	8/17/2026 17:15	WALL	DRYWALL	UNIT 125 Bathroom B	INTACT	WHITE	Negative	<LOD
273	8/17/2026 17:15	WALL	DRYWALL	UNIT 125 Bathroom C	INTACT	WHITE	Negative	<LOD
274	8/17/2026 17:16	WALL	DRYWALL	UNIT 125 Bathroom D	INTACT	WHITE	Negative	<LOD
275	8/17/2026 17:17	WALL	DRYWALL	UNIT 125 Bathroom D	INTACT	WHITE	Negative	<LOD
276	8/17/2026 17:17	DOOR	WOOD	UNIT 125 Bathroom D	INTACT	WHITE	Negative	<LOD
277	8/17/2026 17:18	DOOR	WOOD	UNIT 125 Bathroom D	INTACT	WHITE	Negative	<LOD
278	8/17/2026 17:18	DOOR FRAME	WOOD	UNIT 125 Bathroom D	INTACT	WHITE	Negative	<LOD
279	8/17/2026 17:22	CEILING	DRYWALL	Unit 127 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
280	8/17/2026 17:23	WALL	DRYWALL	Unit 127 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
281	8/17/2026 17:24	WALL	DRYWALL	Unit 127 Kitchen/Living Room B	INTACT	WHITE	Negative	<LOD
282	8/17/2026 17:25	WALL	DRYWALL	Unit 127 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
283	8/17/2026 17:26	WALL	DRYWALL	Unit 127 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
284	8/17/2026 17:27	WINDOW SILL	WOOD	Unit 127 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
285	8/17/2026 17:28	WINDOW FRAME	WOOD	Unit 127 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
286	8/17/2026 17:29	CEILING	DRYWALL	UNIT 127 Bedroom	INTACT	WHITE	Negative	<LOD
287	8/17/2026 17:30	WALL	DRYWALL	UNIT 127 Bedroom A	INTACT	WHITE	Negative	<LOD
288	8/17/2026 17:31	WALL	DRYWALL	UNIT 127 Bedroom B	INTACT	WHITE	Negative	<LOD
289	8/17/2026 17:32	WALL	DRYWALL	UNIT 127 Bedroom C	INTACT	WHITE	Negative	<LOD
290	8/17/2026 17:33	WALL	DRYWALL	UNIT 127 Bedroom D	INTACT	WHITE	Negative	<LOD
291	8/17/2026 17:36	DOOR	WOOD	UNIT 127 Bedroom D	INTACT	WHITE	Negative	<LOD
292	8/17/2026 17:37	DOOR FRAME	WOOD	UNIT 127 Bedroom D	INTACT	WHITE	Negative	0.02
293	8/17/2026 17:37	DOOR FRAME	WOOD	UNIT 127 Bedroom D	INTACT	WHITE	Negative	<LOD
294	8/17/2026 17:37	DOOR FRAME	WOOD	UNIT 127 Bedroom D	INTACT	WHITE	Negative	<LOD
295	8/17/2026 17:38	DOOR FRAME	WOOD	UNIT 127 Bedroom D	INTACT	WHITE	Negative	<LOD
296	8/17/2026 17:39	WINDOW SILL	WOOD	UNIT 127 Bedroom C	INTACT	WHITE	Negative	<LOD
297	8/17/2026 17:40	CEILING	DRYWALL	UNIT 127 Bathroom	INTACT	WHITE	Negative	<LOD
298	8/17/2026 17:41	CEILING	DRYWALL	UNIT 127 Bathroom	INTACT	WHITE	Negative	<LOD
299	8/17/2026 17:42	WALL	DRYWALL	UNIT 127 Bathroom A	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
300	8/17/2026 17:43	WALL	DRYWALL	UNIT 127 Bathroom B	INTACT	WHITE	Negative	<LOD
301	8/17/2026 17:44	WALL	DRYWALL	UNIT 127 Bathroom C	INTACT	WHITE	Negative	<LOD
302	8/17/2026 17:45	WALL	DRYWALL	UNIT 127 Bathroom D	INTACT	WHITE	Negative	0.01
303	8/17/2026 17:48	DOOR	WOOD	UNIT 127 Bathroom D	INTACT	WHITE	Negative	<LOD
304	8/17/2026 17:48	DOOR FRAME	WOOD	UNIT 127 Bathroom D	INTACT	WHITE	Negative	<LOD
305	8/17/2026 17:50	DOOR FRAME	WOOD	Unit 127 Kitchen/Living Room A	INTACT	BEIGE	Negative	<LOD
306	8/17/2026 17:50	DOOR	WOOD	Unit 127 Kitchen/Living Room A	INTACT	BEIGE	Negative	<LOD
307	8/17/2026 17:54	CEILING	DRYWALL	Unit 129 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
308	8/17/2026 17:55	WALL	DRYWALL	Unit 129 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
309	8/17/2026 17:56	WALL	DRYWALL	Unit 129 Kitchen/Living Room B	INTACT	WHITE	Negative	<LOD
310	8/17/2026 17:57	WALL	DRYWALL	Unit 129 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
311	8/17/2026 17:57	WALL	DRYWALL	Unit 129 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
312	8/17/2026 17:58	DOOR	WOOD	Unit 129 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
313	8/17/2026 17:59	DOOR FRAME	WOOD	Unit 129 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
314	8/17/2026 18:00	SILL	WOOD	Unit 129 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
315	8/17/2026 18:01	WINDOW FRAME	WOOD	Unit 129 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
316	8/17/2026 18:03	CEILING	DRYWALL	UNIT 129 Bedroom	INTACT	WHITE	Negative	<LOD
317	8/17/2026 18:04	WALL	DRYWALL	UNIT 129 Bedroom A	INTACT	WHITE	Negative	<LOD
318	8/17/2026 18:05	WALL	DRYWALL	UNIT 129 Bedroom B	INTACT	WHITE	Negative	<LOD
319	8/17/2026 18:06	WALL	DRYWALL	UNIT 129 Bedroom C	INTACT	WHITE	Negative	<LOD
320	8/17/2026 18:06	WALL	DRYWALL	UNIT 129 Bedroom D	INTACT	WHITE	Negative	<LOD
321	8/17/2026 18:07	DOOR	WOOD	UNIT 129 Bedroom D	INTACT	WHITE	Negative	<LOD
322	8/17/2026 18:08	DOOR FRAME	WOOD	UNIT 129 Bedroom D	INTACT	WHITE	Negative	<LOD
323	8/17/2026 18:09	CEILING	DRYWALL	UNIT 129 Bathroom	INTACT	WHITE	Negative	<LOD
324	8/17/2026 18:10	WALL	DRYWALL	UNIT 129 Bathroom A	INTACT	WHITE	Negative	<LOD
325	8/17/2026 18:11	WALL	DRYWALL	UNIT 129 Bathroom B	INTACT	WHITE	Negative	<LOD
326	8/17/2026 18:12	WALL	DRYWALL	UNIT 129 Bathroom C	INTACT	WHITE	Negative	<LOD
327	8/17/2026 18:12	WALL	DRYWALL	UNIT 129 Bathroom D	INTACT	WHITE	Negative	<LOD
328	8/17/2026 18:13	DOOR	WOOD	UNIT 129 Bathroom D	INTACT	WHITE	Negative	<LOD
329	8/17/2026 18:14	FRAME	WOOD	UNIT 129 Bathroom D	INTACT	WHITE	Negative	<LOD
330	8/17/2026 18:14	SILL	WOOD	UNIT 129 Bedroom C	INTACT	WHITE	Negative	<LOD
331	8/17/2026 18:15	FRAME	WOOD	UNIT 129 Bedroom C	INTACT	WHITE	Negative	<LOD
332	8/17/2026 18:20	CEILING	DRYWALL	Unit 124 Kitchen/Living Room	INTACT	WHITE	Negative	0.01
333	8/17/2026 18:21	WALL	DRYWALL	Unit 124 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
334	8/17/2026 18:22	WALL	DRYWALL	Unit 124 Kitchen/Living Room B	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
335	8/17/2026 18:23	WALL	DRYWALL	Unit 124 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
336	8/17/2026 18:24	WALL	DRYWALL	Unit 124 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
337	8/17/2026 18:24	DOOR	WOOD	Unit 124 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
338	8/17/2026 18:25	DOOR FRAME	WOOD	Unit 124 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
339	8/17/2026 18:26	SILL	WOOD	Unit 124 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
340	8/17/2026 18:27	FRAME	WOOD	Unit 124 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
341	8/17/2026 18:28	CEILING	DRYWALL	UNIT 124 Bedroom	INTACT	WHITE	Negative	<LOD
342	8/17/2026 18:29	CEILING	DRYWALL	UNIT 124 Bedroom	INTACT	WHITE	Negative	0.01
343	8/17/2026 18:30	WALL	DRYWALL	UNIT 124 Bedroom A	INTACT	WHITE	Negative	0.01
344	8/17/2026 18:31	WALL	DRYWALL	UNIT 124 Bedroom B	INTACT	WHITE	Negative	<LOD
345	8/17/2026 18:31	WALL	DRYWALL	UNIT 124 Bedroom C	INTACT	WHITE	Negative	<LOD
346	8/17/2026 18:32	WALL	DRYWALL	UNIT 124 Bedroom D	INTACT	WHITE	Negative	0.02
347	8/17/2026 18:32	DOOR FRAME	WOOD	UNIT 124 Bedroom D	INTACT	WHITE	Negative	0.01
348	8/17/2026 18:33	DOOR	WOOD	UNIT 124 Bedroom D	INTACT	WHITE	Negative	0.01
349	8/17/2026 18:34	WINDOW SILL	WOOD	UNIT 124 Bedroom C	INTACT	WHITE	Negative	<LOD
350	8/17/2026 18:34	DOOR	WOOD	UNIT 124 Bedroom C	INTACT	WHITE	Negative	0.01
351	8/17/2026 18:35	DOOR FRAME	WOOD	UNIT 124 Bedroom D	INTACT	WHITE	Negative	0.01
352	8/17/2026 18:36	DOOR	WOOD	UNIT 124 Bathroom D	INTACT	WHITE	Negative	<LOD
353	8/17/2026 18:37	DOOR FRAME	WOOD	UNIT 124 Bathroom D	INTACT	WHITE	Negative	0.01
354	8/17/2026 18:37	CEILING	DRYWALL	UNIT 124 Bathroom	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
355	8/17/2026 18:38	WINDOW	DRYWALL	UNIT 124 Bathroom A	INTACT	WHITE	Negative	<LOD
356	8/17/2026 18:39	WINDOW	DRYWALL	UNIT 124 Bathroom B	INTACT	WHITE	Negative	0.02
357	8/17/2026 18:40	WINDOW	DRYWALL	UNIT 124 Bathroom C	INTACT	WHITE	Negative	0.01
358	8/17/2026 18:40	WINDOW	DRYWALL	UNIT 124 Bathroom D	INTACT	WHITE	Negative	0.01
359	8/17/2026 18:41	DOOR	WOOD	Unit 236 Kitchen/Living Room A	INTACT	WHITE	Negative	0.01
360	8/17/2026 18:41	DOOR FRAME	WOOD	Unit 236 Kitchen/Living Room A	INTACT	WHITE	Negative	0.02
361	8/17/2026 18:41	DOOR FRAME	WOOD	Unit 236 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
362	8/18/2026 9:02	Shutter Cal						
363	8/18/2026 10:23	Shutter Cal						
364	8/18/2026 10:33	Shutter Cal						
365	8/18/2026 10:44	NIST Standard				Yellow	Positive	2.1
366	8/18/2026 10:45	NIST Standard				Yellow	Positive	2.1
367	8/18/2026 10:45	NIST Standard				Yellow	Positive	1.6
368	8/18/2026 10:46	NIST Standard				Yellow	Positive	1.8
369	8/18/2026 10:54	CEILING	DRYWALL	Unit 236 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
370	8/18/2026 10:55	WALL	DRYWALL	Unit 236 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
371	8/18/2026 10:56	WALL	DRYWALL	Unit 236 Kitchen/Living Room B	INTACT	WHITE	Negative	<LOD
372	8/18/2026 10:57	WALL	DRYWALL	Unit 236 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
373	8/18/2026 10:58	WALL	DRYWALL	Unit 236 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
374	8/18/2026 10:59	WINDOW SILL	WOOD	Unit 236 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
375	8/18/2026 11:00	WINDOW FRAME	WOOD	Unit 236 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
376	8/18/2026 11:01	CEILING	DRYWALL	UNIT 236 Bathroom	INTACT	WHITE	Negative	<LOD
377	8/18/2026 11:02	WALL	DRYWALL	UNIT 236 Bathroom A	INTACT	WHITE	Negative	<LOD
378	8/18/2026 11:03	WALL	DRYWALL	UNIT 236 Bathroom B	INTACT	WHITE	Negative	<LOD
379	8/18/2026 11:04	WALL	DRYWALL	UNIT 236 Bathroom C	INTACT	WHITE	Negative	<LOD
380	8/18/2026 11:05	WALL	DRYWALL	UNIT 236 Bathroom D	INTACT	WHITE	Negative	<LOD
381	8/18/2026 11:06	CEILING	DRYWALL	UNIT 236 Bedroom	INTACT	WHITE	Negative	<LOD
382	8/18/2026 11:07	WALL	DRYWALL	UNIT 236 Bedroom A	INTACT	WHITE	Negative	<LOD
383	8/18/2026 11:08	WALL	DRYWALL	UNIT 236 Bedroom B	INTACT	WHITE	Negative	<LOD
384	8/18/2026 11:08	WALL	DRYWALL	UNIT 236 Bedroom C	INTACT	WHITE	Negative	<LOD
385	8/18/2026 11:09	WALL	DRYWALL	UNIT 236 Bedroom D	INTACT	WHITE	Negative	<LOD
386	8/18/2026 11:10	SILL	WOOD	UNIT 236 Bedroom C	INTACT	WHITE	Negative	<LOD
387	8/18/2026 11:11	DOOR	WOOD	UNIT 236 Bedroom D	INTACT	WHITE	Negative	<LOD
388	8/18/2026 11:11	DOOR FRAME	WOOD	UNIT 236 Bedroom C	INTACT	WHITE	Negative	<LOD
389	8/18/2026 11:12	WINDOW SILL	WOOD	UNIT 236 Kitchen/Living Rm C	INTACT	WHITE	Negative	<LOD
390	8/18/2026 11:13	FRONT DOOR	WOOD	UNIT 236 Kitchen/Living Rm A	INTACT	GREEN	Negative	<LOD
391	8/18/2026 11:14	FRONT DOOR FRAME	WOOD	UNIT 236 Kitchen/Living Rm A	INTACT	BEIGE	Negative	<LOD
392	8/18/2026 11:18	CEILING	DRYWALL	Unit 239 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
393	8/18/2026 11:19	WALL	DRYWALL	Unit 239 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
394	8/18/2026 11:20	WALL	DRYWALL	Unit 239 Kitchen/Living Room B	INTACT	WHITE	Negative	<LOD
395	8/18/2026 11:20	WALL	DRYWALL	Unit 239 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
396	8/18/2026 11:21	WALL	DRYWALL	Unit 239 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
397	8/18/2026 11:22	WALL	DRYWALL	Unit 239 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
398	8/18/2026 11:23	WINDOW SILL	WOOD	Unit 239 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
399	8/18/2026 11:24	WINDOW FRAME	WOOD	Unit 239 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
400	8/18/2026 11:26	BALCONY DOOR	WOOD	UNIT 239 Balcony	INTACT	BEIGE	Negative	<LOD
401	8/18/2026 11:27	ALCONY DOOR FRAM	WOOD	UNIT 239 Balcony	INTACT	BROWN	Negative	<LOD
402	8/18/2026 11:28	BALCONY DECK	WOOD	UNIT 239 Balcony	INTACT	YELLOW	Negative	<LOD
403	8/18/2026 11:29	CEILING	DRYWALL	UNIT 239 Bedroom	INTACT	WHITE	Negative	<LOD
404	8/18/2026 11:30	WALL	DRYWALL	UNIT 239 Bedroom A	INTACT	WHITE	Negative	<LOD
405	8/18/2026 11:31	WALL	DRYWALL	UNIT 239 Bedroom B	INTACT	WHITE	Negative	<LOD
406	8/18/2026 11:32	WALL	DRYWALL	UNIT 239 Bedroom C	INTACT	WHITE	Negative	<LOD
407	8/18/2026 11:33	WALL	DRYWALL	UNIT 239 Bedroom D	INTACT	WHITE	Negative	<LOD
408	8/18/2026 11:34	WINDOW SILL	WOOD	UNIT 239 Bedroom C	INTACT	WHITE	Negative	<LOD
409	8/18/2026 11:35	WINDOW FRAME	WOOD	UNIT 239 Bedroom C	INTACT	WHITE	Negative	<LOD
410	8/18/2026 11:35	DOOR	WOOD	UNIT 239 Bedroom D	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
411	8/18/2026 11:36	DOOR FRAME	WOOD	UNIT 239 Bedroom D	INTACT	WHITE	Negative	<LOD
412	8/18/2026 11:36	WINDOW FRAME	WOOD	UNIT 239 Bedroom C	INTACT	WHITE	Negative	<LOD
413	8/18/2026 11:36	WINDOW FRAME	WOOD	UNIT 239 Bedroom C	INTACT	WHITE	Negative	<LOD
414	8/18/2026 11:37	WINDOW FRAME	WOOD	UNIT 239 Bedroom C	INTACT	WHITE	Negative	<LOD
415	8/18/2026 11:38	CEILING	DRYWALL	UNIT 239 Bathroom	INTACT	WHITE	Negative	<LOD
416	8/18/2026 11:39	WALL	DRYWALL	UNIT 239 Bathroom A	INTACT	WHITE	Negative	<LOD
417	8/18/2026 11:39	WALL	DRYWALL	UNIT 239 Bathroom B	INTACT	WHITE	Negative	<LOD
418	8/18/2026 11:40	WALL	DRYWALL	UNIT 239 Bathroom C	INTACT	WHITE	Negative	<LOD
419	8/18/2026 11:41	DOOR	WOOD	UNIT 239 Bathroom D	INTACT	WHITE	Negative	<LOD
420	8/18/2026 11:42	DOOR FRAME	WOOD	UNIT 239 Bathroom D	INTACT	WHITE	Negative	<LOD
421	8/18/2026 11:43	Soffit	WOOD	UNIT 239 Balcony soffit	INTACT	Beige	Negative	<LOD
422	8/18/2026 11:43	DOOR	WOOD	UNIT 239 Balcony Door D	INTACT	WHITE	Negative	<LOD
423	8/18/2026 11:43	DOOR FRAME	WOOD	UNIT 239 Balcony Door Frame D	INTACT	WHITE	Negative	<LOD
424	8/18/2026 11:44	DECK	WOOD	UNIT 239 Balcony Deck	INTACT	WHITE	Negative	<LOD
425	8/18/2026 11:48	CEILING	DRYWALL	Unit 238 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
426	8/18/2026 11:49	WALL	DRYWALL	Unit 238 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
427	8/18/2026 11:50	WALL	DRYWALL	Unit 238 Kitchen/Living Room B	INTACT	WHITE	Negative	<LOD
428	8/18/2026 11:51	WALL	DRYWALL	Unit 238 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
429	8/18/2026 11:51	WALL	DRYWALL	Unit 238 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
430	8/18/2026 11:52	DOOR	WOOD	Unit 238 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
431	8/18/2026 11:53	DOOR FRAME	WOOD	Unit 238 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
432	8/18/2026 11:54	WINDOW SILL	WOOD	Unit 238 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
433	8/18/2026 11:55	WINDOW FRAME	WOOD	Unit 238 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
434	8/18/2026 11:56	BALCONY DOOR	WOOD	UNIT 238 Balcony	INTACT	BEIGE	Negative	<LOD
435	8/18/2026 11:57	ALCONY DOOR FRAM	WOOD	UNIT 238 Balcony	INTACT	BROWN	Negative	<LOD
436	8/18/2026 11:57	BALCONY DECK	WOOD	UNIT 238 Balcony	INTACT	YELLOW	Negative	<LOD
437	8/18/2026 11:58	BALCONY SOFFIT	WOOD	UNIT 238 Balcony	INTACT	BEIGE	Negative	<LOD
438	8/18/2026 12:00	CEILING	DRYWALL	UNIT 238 Bedroom	INTACT	WHITE	Negative	<LOD
439	8/18/2026 12:01	WALL	DRYWALL	UNIT 238 Bedroom A	INTACT	WHITE	Negative	<LOD
440	8/18/2026 12:01	WALL	DRYWALL	UNIT 238 Bedroom B	INTACT	WHITE	Negative	<LOD
441	8/18/2026 12:02	WALL	DRYWALL	UNIT 238 Bedroom C	INTACT	WHITE	Negative	<LOD
442	8/18/2026 12:03	WALL	DRYWALL	UNIT 238 Bedroom D	INTACT	WHITE	Negative	<LOD
443	8/18/2026 12:04	WINDOW SILL	WOOD	UNIT 238 Bedroom	INTACT	WHITE	Negative	<LOD
444	8/18/2026 12:05	WINDOW FRAME	WOOD	UNIT 238 Bedroom	INTACT	WHITE	Negative	<LOD
445	8/18/2026 12:06	DOOR	WOOD	UNIT 238 Bedroom	INTACT	WHITE	Negative	<LOD
446	8/18/2026 12:07	DOOR FRAME	WOOD	UNIT 238 Bedroom	INTACT	WHITE	Negative	<LOD
447	8/18/2026 12:07	DOOR FRAME	WOOD	UNIT 238 Bedroom	INTACT	WHITE	Negative	<LOD
448	8/18/2026 12:07	DOOR FRAME	WOOD	UNIT 238 Bedroom	INTACT	WHITE	Negative	<LOD
449	8/18/2026 12:08	DOOR FRAME	WOOD	UNIT 238 Bedroom	INTACT	WHITE	Negative	<LOD
450	8/18/2026 12:08	DOOR FRAME	WOOD	UNIT 238 Bedroom	INTACT	WHITE	Negative	<LOD
451	8/18/2026 12:09	DOOR FRAME	WOOD	UNIT 238 Bedroom	INTACT	WHITE	Negative	<LOD
452	8/18/2026 12:10	DOOR	WOOD	UNIT 238 Bathroom	INTACT	WHITE	Negative	<LOD
453	8/18/2026 12:11	DOOR FRAME	WOOD	UNIT 238 Bathroom	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
454	8/18/2026 12:12	CEILING	DRYWALL	UNIT 238 Bathroom	INTACT	WHITE	Negative	<LOD
455	8/18/2026 12:13	WALL	DRYWALL	UNIT 238 Bathroom A	INTACT	WHITE	Negative	<LOD
456	8/18/2026 12:14	WALL	DRYWALL	UNIT 238 Bathroom B	INTACT	WHITE	Negative	<LOD
457	8/18/2026 12:15	WALL	DRYWALL	UNIT 238 Bathroom C	INTACT	WHITE	Negative	<LOD
458	8/18/2026 12:15	WALL	DRYWALL	UNIT 238 Bathroom C	INTACT	WHITE	Negative	<LOD
459	8/18/2026 12:16	DOOR	WOOD	UNIT 238 Bathroom C	INTACT	WHITE	Negative	<LOD
460	8/18/2026 12:17	DOOR FRAME	WOOD	UNIT 238 Bathroom C	INTACT	WHITE	Negative	<LOD
461	8/18/2026 12:18	DOOR FRAME	WOOD	UNIT 238 Bathroom C	INTACT	WHITE	Negative	<LOD
462	8/18/2026 12:18	DOOR FRAME	WOOD	UNIT 238 Bathroom C	INTACT	WHITE	Negative	<LOD
463	8/18/2026 12:20	CEILING	DRYWALL	Unit 233 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
464	8/18/2026 12:21	WALL	DRYWALL	Unit 233 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
465	8/18/2026 12:22	WALL	DRYWALL	Unit 233 Kitchen/Living Room B	INTACT	WHITE	Negative	<LOD
466	8/18/2026 12:23	WALL	DRYWALL	Unit 233 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
467	8/18/2026 12:24	WALL	DRYWALL	Unit 233 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
468	8/18/2026 12:33	DOOR	WOOD	Unit 233 Kitchen/Living Room A	INTACT	GREEN	Negative	0.59
469	8/18/2026 12:42	DOOR FRAME	WOOD	Unit 233 Kitchen/Living Room A	INTACT	BEIGE	Negative	0.59
470	8/18/2026 12:43	SOFFIT	WOOD	Unit 233 Balcony	INTACT		Negative	<LOD
471	8/18/2026 12:45	DOOR	WOOD	Unit 233 Balcony	INTACT	BEIGE	Negative	<LOD
472	8/18/2026 12:45	DOOR FRAME	WOOD	Unit 233 Balcony	INTACT	BROWN	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
473	8/18/2026 12:46	BALCONY DECK	WOOD	Unit 233 Balcony	INTACT	YELLOW	Negative	<LOD
474	8/18/2026 12:48	CEILING	DRYWALL	Unit 233 Bedroom	INTACT	WHITE	Negative	<LOD
475	8/18/2026 12:49	WALL	DRYWALL	Unit 233 Bedroom A	INTACT	WHITE	Negative	<LOD
476	8/18/2026 12:49	WALL	DRYWALL	Unit 233 Bedroom B	INTACT	WHITE	Negative	<LOD
477	8/18/2026 12:50	WALL	DRYWALL	Unit 233 Bedroom C	INTACT	WHITE	Negative	<LOD
478	8/18/2026 12:51	WALL	DRYWALL	Unit 233 Bedroom D	INTACT	WHITE	Negative	<LOD
479	8/18/2026 12:52	DOOR	WOOD	Unit 233 Bedroom D	INTACT	WHITE	Negative	<LOD
480	8/18/2026 12:52	DOOR FRAME	WOOD	Unit 233 Bedroom D	INTACT	WHITE	Negative	<LOD
481	8/18/2026 12:53	SILL	WOOD	Unit 233 Bedroom C	INTACT	WHITE	Negative	<LOD
482	8/18/2026 12:54	FRAME	WOOD	Unit 233 Bedroom C	INTACT	WHITE	Negative	<LOD
483	8/18/2026 12:54	CEILING	DRYWALL	Unit 233 Bathroom	INTACT	WHITE	Negative	<LOD
484	8/18/2026 12:55	CEILING	DRYWALL	Unit 233 Bathroom A	INTACT	WHITE	Negative	<LOD
485	8/18/2026 12:56	WALL	DRYWALL	Unit 233 Bathroom A	INTACT	WHITE	Negative	<LOD
486	8/18/2026 12:57	WALL	DRYWALL	Unit 233 Bathroom B	INTACT	WHITE	Negative	<LOD
487	8/18/2026 12:57	WALL	DRYWALL	Unit 233 Bathroom C	INTACT	WHITE	Negative	<LOD
488	8/18/2026 12:58	WALL	DRYWALL	Unit 233 Bathroom D	INTACT	WHITE	Negative	<LOD
489	8/18/2026 12:58	DOOR	WOOD	Unit 233 Bathroom D	INTACT	WHITE	Negative	<LOD
490	8/18/2026 12:59	DOOR FRAME	WOOD	Unit 233 Bathroom D	INTACT	WHITE	Negative	<LOD
491	8/18/2026 12:59	SOFFIT	WOOD	Unit 233 Balcony	INTACT	WHITE	Negative	<LOD
492	8/18/2026 13:00	DOOR FRAME	WOOD	Unit 233 Balcony C	INTACT	WHITE	Negative	<LOD
493	8/18/2026 13:01	DOOR	WOOD	Unit 233 Balcony C	INTACT	WHITE	Negative	<LOD
494	8/18/2026 13:05	CEILING	DRYWALL	Unit 235 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
495	8/18/2026 13:06	WALL	DRYWALL	Unit 235 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
496	8/18/2026 13:06	WALL	DRYWALL	Unit 235 Kitchen/Living Room B	INTACT	WHITE	Negative	<LOD
497	8/18/2026 13:08	WALL	DRYWALL	Unit 235 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
498	8/18/2026 13:08	WALL	DRYWALL	Unit 235 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
499	8/18/2026 13:09	DOOR	DRYWALL	Unit 235 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
500	8/18/2026 13:09	DOOR FRAME	DRYWALL	Unit 235 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
501	8/18/2026 13:10	SILL	DRYWALL	Unit 235 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
502	8/18/2026 13:11	CEILING	DRYWALL	UNIT 235 Bedroom	INTACT	WHITE	Negative	<LOD
503	8/18/2026 13:12	WALL	DRYWALL	UNIT 235 Bedroom A	INTACT	WHITE	Negative	<LOD
504	8/18/2026 13:13	WALL	DRYWALL	UNIT 235 Bedroom B	INTACT	WHITE	Negative	<LOD
505	8/18/2026 13:14	WALL	DRYWALL	UNIT 235 Bedroom C	INTACT	WHITE	Negative	<LOD
506	8/18/2026 13:15	WALL	DRYWALL	UNIT 235 Bedroom D	INTACT	WHITE	Negative	<LOD
507	8/18/2026 13:15	DOOR	WOOD	UNIT 235 Bedroom D	INTACT	WHITE	Negative	<LOD
508	8/18/2026 13:16	DOOR FRAME	WOOD	UNIT 235 Bedroom D	INTACT	WHITE	Negative	<LOD
509	8/18/2026 13:16	SILL	WOOD	UNIT 235 Bedroom C	INTACT	WHITE	Negative	<LOD
510	8/18/2026 13:17	FRAME	WOOD	UNIT 235 Bedroom C	INTACT	WHITE	Negative	<LOD
511	8/18/2026 13:17	DOOR	WOOD	UNIT 235 Balcony	INTACT	BEIGE	Negative	<LOD
512	8/18/2026 13:18	DOOR FRAME	WOOD	UNIT 235 Balcony	INTACT	BEIGE	Negative	<LOD
513	8/18/2026 13:18	DECK	WOOD	UNIT 235 Balcony	INTACT	YELLOW	Negative	<LOD
514	8/18/2026 13:19	SOFFIT	WOOD	UNIT 235 Balcony	INTACT	BEIGE	Negative	<LOD
515	8/18/2026 13:20	WALL	WOOD	UNIT 235 Balcony	INTACT	YELLOW	Negative	<LOD
516	8/18/2026 13:21	CEILING	DRYWALL	UNIT 235 Bathroom	INTACT	WHITE	Negative	<LOD
517	8/18/2026 13:22	WALL	DRYWALL	UNIT 235 Bathroom A	INTACT	WHITE	Negative	<LOD
518	8/18/2026 13:23	WALL	DRYWALL	UNIT 235 Bathroom B	INTACT	WHITE	Negative	<LOD
519	8/18/2026 13:23	WALL	DRYWALL	UNIT 235 Bathroom C	INTACT	WHITE	Negative	<LOD
520	8/18/2026 13:24	WALL	DRYWALL	UNIT 235 Bathroom D	INTACT	WHITE	Negative	<LOD
521	8/18/2026 13:25	WALL	DRYWALL	UNIT 235 Bathroom D	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
522	8/18/2026 13:25	DOOR	WOOD	UNIT 235 Bathroom D	INTACT	WHITE	Negative	<LOD
523	8/18/2026 13:26	DOOR	WOOD	UNIT 235 Bathroom D	INTACT	WHITE	Negative	<LOD
524	8/18/2026 13:27	DOOR FRAME	WOOD	UNIT 235 Bathroom D	INTACT	WHITE	Negative	<LOD
525	8/18/2026 13:27	DOOR FRAME	WOOD	UNIT 235 Bathroom D	INTACT	WHITE	Negative	<LOD
526	8/18/2026 13:28	FRONT DOOR	WOOD	Unit 235 Kitchen/Living Room A	INTACT	BEIGE	Negative	<LOD
527	8/18/2026 13:29	FRONT DOOR	WOOD	Unit 235 Kitchen/Living Room A	INTACT	BEIGE	Negative	<LOD
528	8/18/2026 13:30	FRONT DOOR FRAME	WOOD	Unit 235 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
529	8/18/2026 13:31	BALCONY DOOR	WOOD	UNIT 235 Balcony	INTACT	BEIGE	Negative	<LOD
530	8/18/2026 13:32	ALCONY DOOR FRAM	WOOD	UNIT 235 Balcony	INTACT	BROWN	Negative	<LOD
531	8/18/2026 13:33	BALCONY DECK	WOOD	UNIT 235 Balcony	INTACT	YELLOW	Negative	<LOD
532	8/18/2026 13:34	BALCONY SOFFIT	WOOD	UNIT 235 Balcony	INTACT	YELLOW	Negative	<LOD
533	8/18/2026 13:34	DOOR	WOOD	Unit 261 Kitchen/Living Room A	INTACT	YELLOW	Negative	<LOD
534	8/18/2026 13:39	DOOR FRAME	WOOD	Unit 261 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
535	8/18/2026 13:40	CEILING	GYPSUM	Unit 261 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
536	8/18/2026 13:40	CEILING	GYPSUM	Unit 261 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
537	8/18/2026 13:42	WALL	GYPSUM	Unit 261 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
538	8/18/2026 13:43	WALL	GYPSUM	Unit 261 Kitchen/Living Room B	INTACT	WHITE	Negative	<LOD
539	8/18/2026 13:43	WALL	GYPSUM	Unit 261 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
540	8/18/2026 13:44	WALL	GYPSUM	Unit 261 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
541	8/18/2026 13:44	WINDOW SILL	WOOD	Unit 261 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
542	8/18/2026 13:44	WINDOW FRAME	WOOD	Unit 261 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
543	8/18/2026 13:45	WALL	GYPSUM	Unit 261 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
544	8/18/2026 13:46	WALL	GYPSUM	Unit 261 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
545	8/18/2026 13:47	WINDOW SILL	WOOD	Unit 261 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
546	8/18/2026 13:48	WINDOW FRAME	WOOD	Unit 261 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
547	8/18/2026 13:49	BALCONY DOOR	WOOD	UNIT 261 Balcony	INTACT	BEIGE	Negative	<LOD
548	8/18/2026 13:50	ALCONY DOOR FRAM	WOOD	UNIT 261 Balcony	INTACT	BROWN	Negative	<LOD
549	8/18/2026 13:51	BALCONY DECK	WOOD	UNIT 261 Balcony	INTACT	YELLOW	Negative	<LOD
550	8/18/2026 13:52	BALCONY SOFFIT	WOOD	UNIT 261 Balcony	INTACT	BEIGE	Negative	<LOD
551	8/18/2026 13:53	CEILING	DRYWALL	UNIT 261 Bedroom	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
552	8/18/2026 13:54	WALL	DRYWALL	UNIT 261 Bedroom A	INTACT	WHITE	Negative	<LOD
553	8/18/2026 13:54	WALL	DRYWALL	UNIT 261 Bedroom B	INTACT	WHITE	Negative	<LOD
554	8/18/2026 13:55	WALL	DRYWALL	UNIT 261 Bedroom C	INTACT	WHITE	Negative	<LOD
555	8/18/2026 13:56	WALL	DRYWALL	UNIT 261 Bedroom D	INTACT	WHITE	Negative	<LOD
556	8/18/2026 13:57	WALL	DRYWALL	UNIT 261 Bedroom C	INTACT	WHITE	Negative	<LOD
557	8/18/2026 13:57	WALL	DRYWALL	UNIT 261 Bedroom D	INTACT	WHITE	Negative	<LOD
558	8/18/2026 13:58	WINDOW SILL	WOOD	UNIT 261 Bedroom C	INTACT	WHITE	Negative	<LOD
559	8/18/2026 13:59	WINDOW FRAME	WOOD	UNIT 261 Bedroom C	INTACT	WHITE	Negative	<LOD
560	8/18/2026 14:00	DOOR	WOOD	UNIT 261 Bedroom D	INTACT	WHITE	Negative	<LOD
561	8/18/2026 14:01	DOOR FRAME	WOOD	UNIT 261 Bedroom D	INTACT	WHITE	Negative	<LOD
562	8/18/2026 14:01	DOOR FRAME	WOOD	UNIT 261 Bedroom D	INTACT	WHITE	Negative	<LOD
563	8/18/2026 14:01	DOOR FRAME	WOOD	UNIT 261 Bedroom D	INTACT	WHITE	Negative	<LOD
564	8/18/2026 14:02	CEILING	DRYWALL	UNIT 261 Bathroom	INTACT	WHITE	Negative	<LOD
565	8/18/2026 14:03	WALL	DRYWALL	UNIT 261 Bathroom A	INTACT	WHITE	Negative	<LOD
566	8/18/2026 14:04	WALL	DRYWALL	UNIT 261 Bathroom B	INTACT	WHITE	Negative	<LOD
567	8/18/2026 14:05	WALL	DRYWALL	UNIT 261 Bathroom C	INTACT	WHITE	Negative	<LOD
568	8/18/2026 14:06	WALL	DRYWALL	UNIT 261 Bathroom D	INTACT	WHITE	Negative	<LOD
569	8/18/2026 14:08	DOOR	WOOD	UNIT 261 Bathroom C	INTACT	WHITE	Negative	<LOD
570	8/18/2026 14:09	DOOR FRAME	WOOD	UNIT 261 Bathroom C	INTACT	WHITE	Negative	<LOD
571	8/18/2026 14:10	DOOR FRAME	WOOD	UNIT 261 Bathroom C	INTACT	WHITE	Negative	<LOD
572	8/18/2026 14:26	Shutter Cal						
573	8/18/2026 14:50	NIST Standard				Yellow	Positive	1.4
574	8/18/2026 14:51	NIST Standard				Yellow	Positive	1.6
575	8/18/2026 14:52	NIST Standard				Yellow	Positive	1.4
576	8/18/2026 14:53	WALL	DRYWALL	Management Office A	INTACT	BEIGE	Negative	<LOD
577	8/18/2026 14:55	WALL	DRYWALL	Management Office B	INTACT	BEIGE	Negative	<LOD
578	8/18/2026 14:55	WALL	DRYWALL	Management Office C	INTACT	BEIGE	Negative	<LOD
579	8/18/2026 14:56	WALL	DRYWALL	Management Office D	INTACT	BEIGE	Negative	<LOD
580	8/18/2026 14:57	WINDOW SILL	WOOD	Management Office D	INTACT	GREEN	Negative	<LOD
581	8/18/2026 14:58	DOOR	METAL	Management Office A	INTACT	RED	Negative	<LOD
582	8/18/2026 14:59	DOOR FRAME	WOOD	Management Office A	INTACT	BEIGE	Negative	<LOD
583	8/18/2026 15:00	WALL	DRYWALL	Conference Room A	INTACT	BEIGE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
584	8/18/2026 15:01	WALL	DRYWALL	Conference Room B	INTACT	BEIGE	Negative	<LOD
585	8/18/2026 15:02	WALL	DRYWALL	Conference Room C	INTACT	BEIGE	Negative	<LOD
586	8/18/2026 15:02	WALL	DRYWALL	Conference Room D	INTACT	BEIGE	Negative	<LOD
587	8/18/2026 15:03	DOOR	METAL	Conference Room A	INTACT	RED	Negative	<LOD
588	8/18/2026 15:04	DOOR FRAME	WOOD	Conference Room A	INTACT	BEIGE	Negative	<LOD
589	8/18/2026 15:05	WALL	DRYWALL	Common Restroom A	INTACT	YELLOW	Negative	<LOD
590	8/18/2026 15:06	WALL	DRYWALL	Common Restroom B	INTACT	YELLOW	Negative	<LOD
591	8/18/2026 15:06	WALL	DRYWALL	Common Restroom C	INTACT	YELLOW	Negative	<LOD
592	8/18/2026 15:07	WALL	DRYWALL	Common Restroom D	INTACT	YELLOW	Negative	<LOD
593	8/18/2026 15:08	DOOR	METAL	Common Restroom A	INTACT	RED	Negative	<LOD
594	8/18/2026 15:09	DOOR FRAME	METAL	Common Restroom A	INTACT	RED	Negative	<LOD
595	8/18/2026 15:16	CEILING	DRYWALL	Unit 249 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
596	8/18/2026 15:17	WALL	DRYWALL	Unit 249 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
597	8/18/2026 15:18	WALL	DRYWALL	Unit 249 Kitchen/Living Room B	INTACT	WHITE	Negative	<LOD
598	8/18/2026 15:19	WALL	DRYWALL	Unit 249 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
599	8/18/2026 15:20	WALL	DRYWALL	Unit 249 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
600	8/18/2026 15:21	WINDOW SILL	DRYWALL	Unit 249 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
601	8/18/2026 15:22	WINDOW FRAME	DRYWALL	Unit 249 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
602	8/18/2026 15:23	BALCONY DOOR	WOOD	UNIT 249 Balcony	INTACT	BEIGE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
603	8/18/2026 15:24	ALCONY DOOR FRAM	WOOD	UNIT 249 Balcony	INTACT	BROWN	Negative	<LOD
604	8/18/2026 15:26	WALL	DRYWALL	UNIT 249 Bedroom A	INTACT	BROWN	Negative	<LOD
605	8/18/2026 15:27	WALL	DRYWALL	UNIT 249 Bedroom B	INTACT	BROWN	Negative	<LOD
606	8/18/2026 15:28	WALL	DRYWALL	UNIT 249 Bedroom C	INTACT	BROWN	Negative	<LOD
607	8/18/2026 15:29	WALL	DRYWALL	UNIT 249 Bedroom D	INTACT	BROWN	Negative	<LOD
608	8/18/2026 15:29	DOOR	WOOD	UNIT 249 Bedroom D	INTACT	WHITE	Negative	<LOD
609	8/18/2026 15:30	DOOR	WOOD	UNIT 249 Bedroom D	INTACT	WHITE	Negative	<LOD
610	8/18/2026 15:31	DOOR FRAME	WOOD	UNIT 249 Bedroom D	INTACT	WHITE	Negative	<LOD
611	8/18/2026 15:31	WINDOW FRAME	WOOD	UNIT 249 Bedroom D	INTACT	WHITE	Negative	<LOD
612	8/18/2026 15:32	WINDOW SILL	WOOD	UNIT 249 Bedroom C	INTACT	WHITE	Negative	<LOD
613	8/18/2026 15:40	CEILING	DRYWALL	Unit 253 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
614	8/18/2026 15:41	WALL	DRYWALL	Unit 253 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
615	8/18/2026 15:42	WALL	DRYWALL	Unit 253 Kitchen/Living Room B	INTACT	WHITE	Negative	<LOD
616	8/18/2026 15:43	WALL	DRYWALL	Unit 253 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
617	8/18/2026 15:44	WALL	DRYWALL	Unit 253 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
618	8/18/2026 15:46	WINDOW SILL	WOOD	Unit 253 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
619	8/18/2026 15:47	WINDOW FRAME	WOOD	Unit 253 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
620	8/18/2026 15:47	WINDOW FRAME	WOOD	Unit 253 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
621	8/18/2026 15:48	BALCONY DOOR	WOOD	UNIT 253 Balcony	INTACT	BEIGE	Negative	<LOD
622	8/18/2026 15:49	ALCONY DOOR FRAM	WOOD	UNIT 253 Balcony	INTACT	BROWN	Negative	<LOD
623	8/18/2026 15:50	BALCONY DECK	WOOD	UNIT 253 Balcony	INTACT	YELLOW	Negative	<LOD
624	8/18/2026 15:52	CEILING	DRYWALL	UNIT 253 Bedroom	INTACT	YELLOW	Negative	<LOD
625	8/18/2026 15:53	WALL	DRYWALL	UNIT 253 Bedroom A	INTACT	YELLOW	Negative	<LOD
626	8/18/2026 15:54	WALL	DRYWALL	UNIT 253 Bedroom B	INTACT	YELLOW	Negative	<LOD
627	8/18/2026 15:55	WALL	DRYWALL	UNIT 253 Bedroom C	INTACT	YELLOW	Negative	<LOD
628	8/18/2026 15:56	WALL	DRYWALL	UNIT 253 Bedroom D	INTACT	YELLOW	Negative	<LOD
629	8/18/2026 15:57	DOOR	WOOD	UNIT 253 Bedroom D	INTACT	WHITE	Negative	<LOD
630	8/18/2026 15:58	DOOR FRAME	WOOD	UNIT 253 Bedroom D	INTACT	WHITE	Negative	<LOD
631	8/18/2026 15:59	WINDOW SILL	WOOD	UNIT 253 Bedroom C	INTACT	WHITE	Negative	<LOD
632	8/18/2026 16:00	WINDOW FRAME	WOOD	UNIT 253 Bedroom C	INTACT	WHITE	Negative	<LOD
633	8/18/2026 16:01	CEILING	DRYWALL	UNIT 253 Bathroom A	INTACT	WHITE	Negative	<LOD
634	8/18/2026 16:02	WALL	DRYWALL	UNIT 253 Bathroom B	INTACT	WHITE	Negative	<LOD
635	8/18/2026 16:03	WALL	DRYWALL	UNIT 253 Bathroom C	INTACT	WHITE	Negative	<LOD
636	8/18/2026 16:04	WALL	DRYWALL	UNIT 253 Bathroom D	INTACT	WHITE	Negative	<LOD
637	8/18/2026 16:05	DOOR FRAME	WOOD	UNIT 253 Bathroom D	INTACT	WHITE	Negative	<LOD
638	8/18/2026 16:06	DOOR	WOOD	UNIT 253 Bathroom D	INTACT	WHITE	Negative	<LOD
639	8/18/2026 16:06	FRONT DOOR	WOOD	Unit 253 Kitchen/Living Room A	INTACT	GREEN	Negative	<LOD
640	8/18/2026 16:07	FRONT DOOR FRAME	WOOD	Unit 253 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
641	8/18/2026 16:08	FRONT DOOR FRAME	WOOD	Unit 253 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
642	8/18/2026 16:12	CEILING	DRYWALL	Unit 251 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
643	8/18/2026 16:12	WALL	DRYWALL	Unit 251 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
644	8/18/2026 16:13	WALL	DRYWALL	Unit 251 Kitchen/Living Room B	INTACT	WHITE	Negative	<LOD
645	8/18/2026 16:14	WALL	DRYWALL	Unit 251 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
646	8/18/2026 16:15	WALL	DRYWALL	Unit 251 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
647	8/18/2026 16:17	WINDOW SILL	WOOD	Unit 251 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
648	8/18/2026 16:19	BALCONY DOOR	METAL	UNIT 251 Balcony	INTACT	BEIGE	Negative	<LOD
649	8/18/2026 16:19	BALCONY DOOR TRIM	WOOD	UNIT 251 Balcony	INTACT	BROWN	Negative	<LOD
650	8/18/2026 16:20	BALCONY DECK	WOOD	UNIT 251 Balcony	INTACT	YELLOW	Negative	<LOD
651	8/18/2026 16:21	BALCONY SOFFIT	WOOD	UNIT 251 Balcony	INTACT	BEIGE	Negative	<LOD
652	8/18/2026 16:23	CEILING	DRYWALL	UNIT 251 Bedroom	INTACT	WHITE	Negative	<LOD
653	8/18/2026 16:24	WALL	DRYWALL	UNIT 251 Bedroom A	INTACT	WHITE	Negative	<LOD
654	8/18/2026 16:25	WALL	DRYWALL	UNIT 251 Bedroom B	INTACT	WHITE	Negative	<LOD
655	8/18/2026 16:26	WALL	DRYWALL	UNIT 251 Bedroom C	INTACT	WHITE	Negative	<LOD
656	8/18/2026 16:27	WALL	DRYWALL	UNIT 251 Bedroom D	INTACT	WHITE	Negative	<LOD
657	8/18/2026 16:27	DOOR	WOOD	UNIT 251 Besdroom D	INTACT	BROWN	Negative	<LOD
658	8/18/2026 16:28	DOOR FRAME	WOOD	UNIT 251 Bedroom D	INTACT	BROWN	Negative	<LOD
659	8/18/2026 16:28	DOOR FRAME	WOOD	UNIT 251 Bedroom D	INTACT	BROWN	Negative	<LOD
660	8/18/2026 16:30	WINDOW SILL	WOOD	UNIT 251 Bedroom C	INTACT	WHITE	Negative	<LOD
661	8/18/2026 16:32	CEILING	DRYWALL	UNIT 251 Bathroom	INTACT	WHITE	Negative	<LOD
662	8/18/2026 16:33	WALL	DRYWALL	UNIT 251 Bathroom A	INTACT	WHITE	Negative	<LOD
663	8/18/2026 16:34	WALL	DRYWALL	UNIT 251 Bathroom B	INTACT	WHITE	Negative	<LOD
664	8/18/2026 16:35	WALL	DRYWALL	UNIT 251 Bathroom C	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
665	8/18/2026 16:36	WALL	DRYWALL	UNIT 251 Bathroom D	INTACT	WHITE	Negative	<LOD
666	8/18/2026 16:37	DOOR	WOOD	UNIT 251 Bathroom D	INTACT	BROWN	Negative	<LOD
667	8/18/2026 16:38	DOOR FRAME	WOOD	UNIT 251 Bathroom D	INTACT	BROWN	Negative	<LOD
668	8/18/2026 16:39	FRONT DOOR	WOOD	UNIT 251 Bathroom D	INTACT	GREEN	Negative	<LOD
669	8/18/2026 16:40	FRONT DOOR FRAME	WOOD	UNIT 251 Bathroom D	INTACT	WHITE	Negative	<LOD
670	8/18/2026 16:42	CEILING	DRYWALL	Unit 255 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
671	8/18/2026 16:43	WALL	DRYWALL	Unit 255 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
672	8/18/2026 16:44	WALL	DRYWALL	Unit 255 Kitchen/Living Room B	INTACT	WHITE	Negative	<LOD
673	8/18/2026 16:45	WALL	DRYWALL	Unit 255 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
674	8/18/2026 16:46	WALL	DRYWALL	Unit 255 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
675	8/18/2026 16:47	WALL	DRYWALL	Unit 255 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
676	8/18/2026 16:48	WINDOW SIL	DRYWALL	Unit 255 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
677	8/18/2026 16:50	BALCONY DOOR	WOOD	UNIT 255 Balcony	INTACT	BEIGE	Negative	<LOD
678	8/18/2026 16:51	ALCONY DOOR FRAM	WOOD	UNIT 255 Balcony	INTACT	BROWN	Negative	<LOD
679	8/18/2026 16:51	BALCONY SOFFIT	WOOD	UNIT 255 Balcony	INTACT	BEIGE	Negative	<LOD
680	8/18/2026 16:53	CEILING	DRYWALL	UNIT 255 Bedroom	INTACT	WHITE	Negative	<LOD
681	8/18/2026 16:54	WALL	DRYWALL	UNIT 255 Bedroom A	INTACT	WHITE	Negative	<LOD
682	8/18/2026 16:55	WALL	DRYWALL	UNIT 255 Bedroom B	INTACT	WHITE	Negative	<LOD
683	8/18/2026 16:56	WALL	DRYWALL	UNIT 255 Bedroom C	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
684	8/18/2026 16:57	WALL	DRYWALL	UNIT 255 Bedroom D	INTACT	WHITE	Negative	<LOD
685	8/18/2026 16:57	DOOR	WOOD	UNIT 255 Bedroom D	INTACT	WHITE	Negative	<LOD
686	8/18/2026 16:58	DOOR FRAME	WOOD	UNIT 255 Bedroom D	INTACT	WHITE	Negative	<LOD
687	8/18/2026 16:59	WINDOW SILL	WOOD	UNIT 255 Bedroom C	INTACT	WHITE	Negative	<LOD
688	8/18/2026 17:01	CEILING	DRYWALL	UNIT 255 Bathroom	INTACT	WHITE	Negative	<LOD
689	8/18/2026 17:01	WALL	DRYWALL	UNIT 255 Bathroom A	INTACT	WHITE	Negative	<LOD
690	8/18/2026 17:02	WALL	DRYWALL	UNIT 255 Bathroom B	INTACT	WHITE	Negative	<LOD
691	8/18/2026 17:03	WALL	DRYWALL	UNIT 255 Bathroom C	INTACT	WHITE	Negative	<LOD
692	8/18/2026 17:03	WALL	DRYWALL	UNIT 255 Bathroom D	INTACT	WHITE	Negative	<LOD
693	8/18/2026 17:04	WALL	DRYWALL	UNIT 255 Bathroom C	INTACT	WHITE	Negative	<LOD
694	8/18/2026 17:05	WALL	DRYWALL	UNIT 255 Bathroom C	INTACT	WHITE	Negative	<LOD
695	8/18/2026 17:05	DOOR	WOOD	UNIT 255 Bathroom D	INTACT	WHITE	Negative	<LOD
696	8/18/2026 17:06	DOOR FRAME	WOOD	UNIT 255 Bathroom D	INTACT	WHITE	Negative	<LOD
697	8/18/2026 17:08	FRONT DOOR	WOOD	Unit 255 Kitchen/Living Room	INTACT	BEIGE	Negative	<LOD
698	8/18/2026 17:09	FRONT DOOR FRAME	WOOD	Unit 255 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
699	8/18/2026 17:10	WINDOW SILL	WOOD	Unit 255 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
700	8/18/2026 17:10	WINDOW FRAME	WOOD	Unit 255 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
701	8/18/2026 17:13	CEILING	DRYWALL	Unit 252 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
702	8/18/2026 17:14	CEILING	DRYWALL	Unit 252 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
703	8/18/2026 17:15	WALL	DRYWALL	Unit 252 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
704	8/18/2026 17:16	WALL	DRYWALL	Unit 252 Kitchen/Living Room B	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
705	8/18/2026 17:17	WALL	DRYWALL	Unit 252 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
706	8/18/2026 17:18	WALL	DRYWALL	Unit 252 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
707	8/18/2026 17:19	DOOR	WOOD	Unit 252 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
708	8/18/2026 17:19	DOOR FRAME	WOOD	Unit 252 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
709	8/18/2026 17:21	WALL	DRYWALL	Unit 252 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD
710	8/18/2026 17:21	WALL	DRYWALL	Unit 252 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
711	8/18/2026 17:22	WINDOW FRAME	DRYWALL	Unit 252 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
712	8/18/2026 17:23	WINDOW SILL	WOOD	Unit 252 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
713	8/18/2026 17:24	BALCONY DOOR	METAL	UNIT 252 Balcony	INTACT	BEIGE	Negative	<LOD
714	8/18/2026 17:25	ALCONY DOOR FRAM	WOOD	UNIT 252 Balcony	INTACT	BROWN	Negative	<LOD
715	8/18/2026 17:27	CEILING	DRYWALL	UNIT 252 Bedroom	INTACT	WHITE	Negative	<LOD
716	8/18/2026 17:27	WALL	DRYWALL	UNIT 252 Bedroom A	INTACT	WHITE	Negative	<LOD
717	8/18/2026 17:28	WALL	DRYWALL	UNIT 252 Bedroom B	INTACT	WHITE	Negative	<LOD
718	8/18/2026 17:29	WALL	DRYWALL	UNIT 252 Bedroom C	INTACT	WHITE	Negative	<LOD
719	8/18/2026 17:29	WALL	DRYWALL	UNIT 252 Bedroom D	INTACT	WHITE	Negative	<LOD
720	8/18/2026 17:30	DOOR	WOOD	UNIT 252 Bedroom D	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
721	8/18/2026 17:31	DOOR FRAME	WOOD	UNIT 252 Bedroom D	INTACT	WHITE	Negative	<LOD
722	8/18/2026 17:31	WINDOW SILL	WOOD	UNIT 252 Bedroom C	INTACT	WHITE	Negative	<LOD
723	8/18/2026 17:32	CEILING	DRYWALL	UNIT 252 Bathroom	INTACT	WHITE	Negative	<LOD
724	8/18/2026 17:33	CEILING	DRYWALL	UNIT 252 Bathroom A	INTACT	WHITE	Negative	<LOD
725	8/18/2026 17:33	CEILING	DRYWALL	UNIT 252 Bathroom B	INTACT	WHITE	Negative	<LOD
726	8/18/2026 17:34	CEILING	DRYWALL	UNIT 252 Bathroom C	INTACT	WHITE	Negative	<LOD
727	8/18/2026 17:35	WALL	DRYWALL	UNIT 252 Bathroom D	INTACT	WHITE	Negative	<LOD
728	8/18/2026 17:35	SILL	WOOD	UNIT 252 Bathroom C	INTACT	WHITE	Negative	<LOD
729	8/18/2026 17:37	FRAME	WOOD	UNIT 252 Bathroom C	INTACT	WHITE	Negative	<LOD
730	8/18/2026 17:37	WALL	DRYWALL	UNIT 252 Bathroom B	INTACT	WHITE	Negative	<LOD
731	8/18/2026 17:38	DOOR	WOOD	UNIT 252 Bathroom D	INTACT	WHITE	Negative	<LOD
732	8/18/2026 17:39	DOOR FRAME	WOOD	UNIT 252 Bathroom D	INTACT	WHITE	Negative	<LOD
733	8/18/2026 17:40	FRONT DOOR	WOOD	Unit 252 Kitchen/Living Room A	INTACT	BROWN	Negative	<LOD
734	8/18/2026 17:41	FRONT DOOR FRAME	WOOD	Unit 252 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
735	8/18/2026 17:45	CEILING	DRYWALL	Unit 270 Kitchen/Living Room	INTACT	WHITE	Negative	<LOD
736	8/18/2026 17:46	WALL	DRYWALL	Unit 270 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
737	8/18/2026 17:47	WALL	DRYWALL	Unit 270 Kitchen/Living Room B	INTACT	WHITE	Negative	<LOD
738	8/18/2026 17:48	WALL	DRYWALL	Unit 270 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
739	8/18/2026 17:48	WALL	DRYWALL	Unit 270 Kitchen/Living Room D	INTACT	WHITE	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
740	8/18/2026 17:49	DOOR	DRYWALL	Unit 270 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
741	8/18/2026 17:50	DOOR FRAME	DRYWALL	Unit 270 Kitchen/Living Room A	INTACT	WHITE	Negative	<LOD
742	8/18/2026 17:51	SILL	WOOD	Unit 270 Kitchen/Living Room C	INTACT	WHITE	Negative	<LOD
743	8/18/2026 17:52	BALCONY DOOR	METAL	Unit 270 Balcony	INTACT	BEIGE	Negative	<LOD
744	8/18/2026 17:53	ALCONY DOOR FRAM	WOOD	Unit 270 Balcony	INTACT	BROWN	Negative	<LOD
745	8/18/2026 17:53	ALCONY DOOR FRAM	WOOD	Unit 270 Balcony	INTACT	BROWN	Negative	<LOD
746	8/18/2026 17:54	CEILING	DRYWALL	Unit 270 Bedroom	INTACT	WHITE	Negative	<LOD
747	8/18/2026 17:55	WALL	DRYWALL	Unit 270 Bedroom A	INTACT	WHITE	Negative	<LOD
748	8/18/2026 17:56	WALL	DRYWALL	Unit 270 Bedroom B	INTACT	WHITE	Negative	<LOD
749	8/18/2026 17:57	WALL	DRYWALL	Unit 270 Bedroom C	INTACT	WHITE	Negative	<LOD
750	8/18/2026 17:57	WALL	DRYWALL	Unit 270 Bedroom D	INTACT	WHITE	Negative	<LOD
751	8/18/2026 17:58	SILL	WOOD	Unit 270 Bedroom C	INTACT	WHITE	Negative	<LOD
752	8/18/2026 17:58	FRAME	WOOD	Unit 270 Bedroom C	INTACT	WHITE	Negative	<LOD
753	8/18/2026 17:59	DOOR	WOOD	Unit 270 Bedroom D	INTACT	WHITE	Negative	<LOD
754	8/18/2026 17:59	FRAME	WOOD	Unit 270 Bedroom D	INTACT	WHITE	Negative	<LOD
755	8/18/2026 18:00	CEILING	DRYWALL	Unit 270 Bathroom	INTACT	WHITE	Negative	<LOD
756	8/18/2026 18:01	WALL	DRYWALL	Unit 270 Bathroom A	INTACT	WHITE	Negative	<LOD
757	8/18/2026 18:02	WALL	DRYWALL	Unit 270 Bathroom B	INTACT	WHITE	Negative	<LOD
758	8/18/2026 18:03	WALL	DRYWALL	Unit 270 Bathroom C	INTACT	WHITE	Negative	<LOD
759	8/18/2026 18:04	WALL	DRYWALL	Unit 270 Bathroom D	INTACT	WHITE	Negative	<LOD
760	8/18/2026 18:05	DOOR	WOOD	Unit 270 Bathroom D	INTACT	WHITE	Negative	<LOD
761	8/18/2026 18:06	DOOR FRAME	WOOD	Unit 270 Bathroom D	INTACT	WHITE	Negative	<LOD
762	8/18/2026 18:07	DOOR	METAL	Unit 270 Balcony	INTACT	BEIGE	Negative	<LOD
763	8/18/2026 18:08	DOOR FRAME	WOOD	Unit 270 Balcony	INTACT	BEIGE	Negative	<LOD
764	8/18/2026 18:08	SOFFIT	WOOD	Unit 270 Balcony	INTACT	BEIGR	Negative	<LOD
765	8/18/2026 18:09	DECK	WOOD	Unit 270 Balcony	INTACT	YELLOW	Negative	<LOD

Reading No	Time	Component	Substrate	Side	Condition	Color	Results	Lead (mg/cm2)
766	8/18/2026 18:14	WALL	DRYWALL	Community Room Kitchen A	INTACT	YELLOW	Negative	<LOD
767	8/18/2026 18:14	WALL	DRYWALL	Community Room Kitchen B	INTACT	YELLOW	Negative	<LOD
768	8/18/2026 18:15	WALL	DRYWALL	Community Room Kitchen B	INTACT	YELLOW	Negative	<LOD
769	8/18/2026 18:16	WALL	DRYWALL	Community Room Kitchen C	INTACT	YELLOW	Negative	<LOD
770	8/18/2026 18:17	WALL	DRYWALL	Community Room Kitchen D	INTACT	YELLOW	Negative	<LOD
771	8/18/2026 18:18	WALL	DRYWALL	Community Room A	INTACT	YELLOW	Negative	<LOD
772	8/18/2026 18:19	COLUMN	WOOD	Community Room A	INTACT	GRAY	Negative	<LOD
773	8/18/2026 18:20	COLUMN	WOOD	Community Room B	INTACT	GRAY	Negative	<LOD
774	8/18/2026 18:21	COLUMN	WOOD	Community Room B	INTACT	GRAY	Negative	<LOD
775	8/18/2026 18:22	DOOR	WOOD	Community Room D	INTACT	GRAY	Negative	<LOD
776	8/18/2026 18:22	DOOR FRAME	WOOD	Community Room D	INTACT	GRAY	Negative	<LOD
777	8/18/2026 18:23	WINDOW SILL	WOOD	Community Room D	INTACT	GRAY	Negative	<LOD
778	8/18/2026 18:24	WALL	DRYWALL	Community Room D	INTACT	YELLOW	Negative	<LOD
779	8/18/2026 18:25	WALL	DRYWALL	Community Room D	INTACT	YELLOW	Negative	<LOD
780	8/18/2026 18:28	WALL	DRYWALL	Community Room D	INTACT	YELLOW	Negative	<LOD
781	8/18/2026 18:29	WALL	DRYWALL	Community Room D	INTACT	YELLOW	Negative	<LOD
782	8/18/2026 18:30	WALL	DRYWALL	Community Room D	INTACT	YELLOW	Negative	<LOD
783	8/18/2026 18:31	WINDOW FRAME	WOOD	Building Exterior A	INTACT	YELLOW	Negative	0.59
784	8/18/2026 18:32	WINDOW FRAME	WOOD	Building Exterior B	INTACT	YELLOW	Negative	<LOD
785	8/18/2026 18:33	WINDOW FRAME	WOOD	Building Exterior C	INTACT	YELLOW	Negative	0.58
786	8/18/2026 18:34	WINDOW FRAME	WOOD	Building Exterior D	INTACT	YELLOW	Negative	0.59
787	8/18/2026 18:35	WINDOW FRAME	WOOD	Building Exterior A	INTACT	YELLOW	Negative	0.54

PBS

XRF CALIBRATION CHECK TEST RESULTS

XRF Serial No.: 102877 Date: 8/17/26 - 8/18/26

Address/Unit Number: XLp 300 109cd

Device: Thermo Scientific Niton Analyzer XLp 300

Contractor: Apex

Inspector Name: Janet Murphy Signature: Janet Murphy

NIST SRM used: 1.53 +or- 0.09 mg/cm² **Calibration Check tolerance used:** SRM 2572 mg/cm²

FIRST CALIBRATION CHECK: 8/17/26

NIST SRM						First Average	Difference Between First Average and NIST SRM*
First Reading		Second Reading		Third Reading			
(16.)	1.4	(11.)	1.5	(12.)	1.5	1.47	0.06

SECOND CALIBRATION CHECK: 8/17/26

NIST SRM						First Average	Difference Between First Average and NIST SRM*
First Reading		Second Reading		Third Reading			
(174)	1.5	(175)	1.5	(176)	1.3	1.43	0.1

THIRD CALIBRATION CHECK (IF REQUIRED): 8/18/26

NIST SRM						First Average	Difference Between First Average and NIST SRM*
First Reading		Second Reading		Third Reading			
(366)	2.1	(367)	1.6	(368)	1.8	1.83	0.3

FOURTH CALIBRATION CHECK (IF REQUIRED): 8/18/26

NIST SRM						First Average	Difference Between First Average and NIST SRM*
First Reading		Second Reading		Third Reading			
(573)	1.4	(574)	1.6	(575)	1.4	1.46	0.07

* If the difference of the Calibration Check Average from the NIST SRM film value is greater than the specified Calibration Check tolerance for this device, consult the manufacturer's recommendations to bring the instrument back into control. Retest all testing combinations tested since the last successful Calibration Check test.

TAB 2

Certifications

STATE OF WASHINGTON

Department of Commerce

Lead-Based Paint Activities Program

Janet Joan Murphy

Has fulfilled the certification requirements of
WAC 365-230
and has been certified to conduct lead based paint activities as a
Risk Assessor.

Certification #	Issuance Date	Expiration Date
0258	03/21/2025	03/08/2028

STATE OF WASHINGTON

Department of Commerce

Lead-Based Paint Activities Firm

PBS Engineering & Environmental Inc.

Has fulfilled the certification requirements of
WAC 365-230
and has been certified to conduct lead based paint activities.

Certification #	Issuance Date	Expiration Date
178	03/21/2025	09/03/2028